

Meeting of the Mashpee Planning Board
Wednesday, July 1, 2020
Waquoit Meeting Room
Mashpee Town Hall
16 Great Neck Road North
Mashpee, MA 02649
7:00 PM

Virtual / Remote Meeting

Broadcast Live on Local Channel 18

Call in Conference Number: 508-539-1400 extension 8585

Streamed Live on the Town of Mashpee Website: https://www.mashpeema.gov/channel-18

Call Meeting to Order

Pledge of Allegiance

Reorganization of Board Officers

Board Representatives and Assignments to Committees, Commissions and Boards

Approval of Minutes

Review of meeting minutes from June 17, 2020

Public Hearings

7:10 PM - Southworth Mashpee Properties LLC

Pursuant to Massachusetts General Laws, Chapter 40A Section 11, the Mashpee Planning Board will hold a public hearing on Wednesday, June 17, 2020 at 7:10PM at the Mashpee Town Hall, 16 Great Neck Road North, to consider an application from Southworth Mashpee Properties LLC, property owner, to modify the Willowbend Country Club Special Permit. The applicant proposes to construct a 6-unit multifamily residential townhouse structure to be known as the Clubhouse Villas on a 40,009 square foot parcel located north of Quinaquisset Avenue and found on Assessors Map 69 Block 117.

New Business

• C. Rowley Billing – June 2020

Town Planner Report

- Update to Subdivision Rules and Regulations and Special Permit Regulations
- Stormwater Task Force

Consulting Engineer's Report

• Cape Cod Coffee Update

Correspondence

- Pierce Atwood Re: South Cape Village Notice of Intent to Sell and Transfer Special Permit
- Falmouth Board of Appeals Notices
- May 2020 Discharge Monitoring Report for South Cape Village N = 5.1
- April 2020 Discharge Monitoring Report for South Cape Village Plant met all permit effluent discharge requirements for April 2020. No influent sample was collected due to Whitewaters Safety Policy pertaining to COVID-19.
- March 2020 Discharge Monitoring Report for South Cape Village N= 6.0
- February 2020 Discharge Monitoring Report for South Cape Village N= 7.1
- January 2020 Discharge Monitoring Report for South Cape Village N=15.60
- December 2019 Discharge Monitoring Report for South Cape Village No flow in December due to plant upgrade work
- November 2019 Discharge Monitoring Report for South Cape Village N= 4.52

Adjournment

Mashpee Planning Board Minutes of Meeting June 17, 2020 at 7:00 p.m.

Mashpee Town Hall-16 Great Neck Road North Virtual/Remote Meeting-Call In (508) 539-1400 x8585 Broadcast Live on Local Channel 18

Present: Chairman Mary Waygan, Joe Cummings, Dennis Balzarini, John (Jack) Phelan, Joseph

Callahan, Robert (Rob) Hansen (Alt.)

Also Present: Evan Lehrer-Town Planner, Charles Rowley-Consultant Engineer

CALL TO ORDER

The Chair welcomed attendees and read a statement regarding the order of Governor Baker suspending provisions of the Open Meeting Law issued March 12, 2020. The meeting was being live streamed and could be viewed at www.mashpeema.gov/channel18. Viewers wishing to provide comment could call (508) 539-1400, extension 8585, to share public comment.

Attendance was taken by roll call with Mr. Balzarini, Mr. Cummings, Mr. Phelan, Mr. Callahan, Chairman Waygan and Mr. Hansen stating their presence. The Town of Mashpee Planning Board meeting was opened by Chairman Waygan, with a quorum, by remote participation at 7:00 p.m. on Wednesday, June 17, 2020 and the Pledge of Allegiance was recited.

The Chair expressed thanks and appreciation to Mr. Cummings, whose term would be completed at the close of this meeting. The Chair thanked Mr. Cummings for his many years of dedication and hard work on the Planning Board. Committee members all expressed their thanks and appreciation to Mr. Cummings.

APPROVAL OF MINUTES—June 3, 2020

Corrections offered by both Mr. Rowley and Mr. Lehrer were considered and accepted by members of the Board.

MOTION: Mr. Balzarini made a motion to approve the minutes of June 3^{rd,} 2020 as amended by Mr. Rowley and Mr. Lehrer. Mr. Callahan seconded the motion. Roll call vote: Mr. Balzarinives; Mr. Cummings-yes; Mr. Phelan-abstained; Mr. Callahan-yes; Chairman Waygan-yes

APPROVAL NOT REQUIRED

Applicant: Sakonnet Realty Trust and Paul & Donna Gardner

Location: 4 & 8 Sakonnet Drive, Mashpee (Assessor's Map 58, Parcels 23 & 29)

Request: Create two new registered unbuildable lots with court assigned numbers 2200 and 2202 along the shore of Johns Pond.

The Chair read the request and recognized Steve Doyle who discussed the application to create two unbuildable lots, lot 2199 and 2200. The Chair had no comments. Mr. Rowley confirmed that he had been in contact with the applicant and indicated his satisfaction, adding that the rights of others to pass and repass would be preserved. Lot 2043, with a dashed line was of no significance and had been established previously. There was discussion regarding prior ownership and it was believed that it was common ownership and Mr. Doyle confirmed that all persons lawfully holding rights to access would continue to have access. Mr. Doyle confirmed that the property would continue to be waterfront and the change was not intended for assessment purposes.

MOTION: Mr. Balzarini made a motion that the plan was an Approval Not Required. Mr. Cummings seconded the motion. Roll call vote: Mr. Balzarini-yes; Mr. Cummings-yes; Mr. Phelan-yes; Mr. Callahan-yes; Chairman Waygan-yes

The Chair reminded the Board that Mr. Lehrer was authorized to sign the plan. Mr. Lehrer confirmed that authorization was recorded with Land Court.

NEW BUSINESS

OLD BUSINESS

South Cape Village-The Chair inquired about the status of new ownership of South Cape Village. Mr. Lehrer responded that he had sent a letter and learned that there would be no sale of the property at this time and he would include a copy of the letter in the next meeting's packet, as correspondence had been received after posting of the agenda.

CHAIRMAN'S REPORT

The Chair reported that, due to an error in abutter noticing, the Public Hearing needed to be readvertised for the next meeting on July 1. Public comment for the Hearing would be taken by the advertised phone line.

MOTION: Mr. Balzarini made a motion to set the Public Hearing for Southworth Mashpee Properties LLC, July 1 at 7:10 p.m. Mr. Phelan seconded the motion. Roll call vote: Mr. Balzarini-yes; Mr. Cummings-yes; Mr. Phelan-yes; Mr. Callahan-yes; Chairman Waygan-yes

TOWN PLANNER REPORT

Cape Cod Coffee Update & Discussion-Mr. Lehrer reported that Cape Cod Coffee was nearing completion of construction, but that an abutter expressed concern regarding tree clearing in an area that was to remain naturally vegetated. Mr. Lehrer confirmed that tree clearing had occurred beyond the staking, and contacted Mr. Rowley to inspect whether there was a violation to the permit. Mr. Rowley inspected and provided a report, a copy of which was also given to the owner. Mr. Rowley reported that he had taken measurements, based on the location of the building, finding that the toe of the slope was located at the limit of clearing, as shown on the plan. Mr. Rowley referenced the previous plan replacing the retaining wall with a stockade fence, however, the stockade fence was now being located at the top of the slope. Board members reviewed photos provided by Mr. Rowley, who identified areas between the location of the fence and area at the edge of the brush, which should have been kept natural. The site contractor indicated that he did not cut trees, but removed underbrush to add fill. Material would be removed once the area was loamed and seeded. Mr. Rowley stated that there was technically a violation of the area shown on the site plan to remain in its natural state. Mr. Rowley had suggested the development of a plan identifying the trees, shrubs and loam and seed to be added to the site to revegetate. Mr. Balzarini inquired whether they planned to remove the dirt from around the trees and Mr. Rowley responded that the contractor agreed to remove anything around the tree. The Chair noted that their letter did not state they would remove the dirt from around the trees, but Mr. Rowley stated that the contractor told him they would do so. Mr. Phelan noted that their letter indicated that any disturbed area would be returned to its prior natural state once completed. The Chair expressed concern that the dirt required removal, and was not clearly stated.

MOTION: Mr. Balzarini made a motion to clearly send a message through the Town Engineer that the excess fill, as part of the process, be removed. Mr. Cummings seconded the motion.

Mr. Phelan stated his assumption that the letter indicated it would be returned to its natural state, meaning that the fill would be removed. Although the contractor informed Mr. Rowley, the Chair indicated that it had not been stated in writing and expressed her preference that the request be clear.

Roll call vote: Mr. Balzarini-yes; Mr. Cummings-yes; Mr. Phelan-yes; Mr. Callahan-yes; Chairman Waygan-yes

Mr. Rowley agreed to convey the information. Mr. Rowley also reported that a sidewalk had been added, although the last plan approved by the Planning Board had removed the sidewalk in a minor modification, at the request of the applicant. Mr. Rowley confirmed that the turning radius would not be impacted. In addition, binder had been added without contacting Mr. Rowley. Additional items needed to be addressed to be compliant with the site plan. Additional documentation regarding drainage was needed and Mr. Rowley anticipated another inspection to review the top coat and other minor items. The Chair inquired how the change regarding the sidewalk, returning to their original plan, would be properly documented and Mr. Rowley suggested that documentation would be in the form of tonight's acknowledgement. There was discussion regarding the necessity of a motion since the sidewalk was part of the original plan, and the consensus of the Board was that no motion was necessary

CORRESPONDENCE

- -Falmouth Board of Appeals Notices
- -Town of Barnstable Public Hearing Notice
- -April 2020 Discharge Monitoring Report for South Cape Village-Plant met all permit effluent discharge requirements for April 2020. No influent sample was collected due to Whitewaters Safety Policy pertaining to COVID-19.
- -March 2020 Discharge Monitoring Report for South Cape Village N=6.0
- -February 2020 Discharge Monitoring Report for South Cape Village N=7.1
- -January 2020 Discharge Monitoring Report for South Cape Village N=15.60
- -December 2019 Discharge Monitoring Report for South Cape Village-no flow due to plant upgrade work
- -November 2019 Discharge Monitoring Report for South Cape Village N=4.52

ADJOURNMENT

MOTION: Mr. Balzarini made a motion to adjourn. Mr. Cummings seconded the motion. All voted unanimously. Roll call vote: Mr. Balzarini-yes; Mr. Cummings-yes; Mr. Phelan-yes; Mr. Callahan-yes; Chairman Waygan-yes. The meeting adjourned at 7:32 p.m.

Respectfully submitted,

Jennifer M. Clifford Board Secretary

LIST OF DOCUMENTS PROVIDED

Documentation available online at Mashpee's Planning Board website page



MEMORANDUM

TO:

Andrew R. Gottlieb, Chair

Board of Selectmen

FROM: Mary E. Waygan, Chair

Planning Board

DATE:

July 1, 2019

RE:

Planning Board Representative to Other Boards and Committees

CC:

Stephanie Coleman, Administrative Secretary

Rodney Collins, Town Manager

At the regular meeting of the Planning Board on June 19, 2019 the following appointments were made understanding the Board of Selectmen may then confirm and/or appoint:

Appointment by vote of the Planning Board:

- Dennis H. Balzarini to the Historic District Commission
- Joseph Cummings to the Environmental Oversight Committee
- John Phelan to the MMR Military Civilian Council
- Mary E. Waygan to the Community Preservation Committee

Appointment by the Chair of the Planning Board:

Joseph Callahan to Design Review

Mr. Cummins received the attached correspondence dated June 20, 2019 stating he was appointed to Design Review. Would you kindly modify this record, or take any additional Board action you feel is necessary to modify this appointment, as Mr. Callahan was appointed to Design Review by the Planning Board Chair per Town of Mashpee Zoning Bylaw Section 174-48.C., also attached here.

Thank you!

Planning Board Representative to Other Boards and Committees

Dennis Balzarini

Historic District Commission

Joseph Cummings

Environmental Oversight Committee

John Phelan

MMR Military Civilian Council

Mary E. Waygan

Community Preservation Committee

Joseph Callahan

Design Review



Town of Mushpee

Planning Board

We Green Nork Road Abrili Mashpet, Mitsarchusens 172049

APPLICATION FOR SPECIAL PERMIT MODIFICATION

Date received by Town Clerk: May 20, 2020 Town Clerk Signature / Seal: Webotal War
The undersigned hereby applies for a Modification of the Special Permit approved by the Mashpee Planning Board on April 15, 1567 for a project entitled Willowbiad
The original Special Permit and any Modifications have been recorded in the Barnstable County Registry of Deeds at the following Book(s) and Page(s): Bh 5707 Page 391
Name of Applicant Southwarth Mask pee Paper haphone 508-535-5200
Address 130 Willowbend Drive, Mashpel
Owner, if differentPhone
Address
Attach copies of (a) most recent recorded deed and (b) tax bill or Assessors' certification. Deed of property recorded in Barnstable County Registry Book 2/395 Page 205 or Land Court Certificate of Title No.
Location and description of property: North of Quinnagorett Ave
Lot G-12A2 in Plan Book 657, Page 51
Mashpee Assessors Map(s) and Block(s):
How long have you owned the property? By elivs Section(s) of the Zoning Bylaw which require(s) the permit you seek 9.3 and 5.4 of
Present use of property: Vacant golf course
Description of proposed modification (attach plans and documents as required by the Zoning By-law and Special Permit Regulations): See attachal cover letter
Signature of Owner or Authorized Representative
Attach written authorization signed by owner.

JACK McELHINNEY Attorney at Law

63 Shore Road, Suite 23 Winchester, MA 01890 jmcelhin@aol.com

Phone: 781.729.7299 Fax: 781.721.3419 Cell: 617.816.4092

May 19, 2020

By Hand Delivery

Planning Board Town of Mashpee 16 Great Neck Road North Mashpee, MA 02649

Attn: Evan Lehrer, Town Planner

Re: Willowbend Country Club – Request for Modification No. 35 of Special Permit

Dear Members of the Planning Board:

Enclosed please find the application of Southworth Mashpee Properties LLC for a modification of the Special Permit for Willowbend Country Club. A check in the amounts of \$880.00 is included to cover application fees. The application seeks approval to construct an additional six units in a three-story building on a one-acre parcel located north of Quinnaquisett Ave and south of the existing golf shop. The building will be identical to the existing three-story villa buildings on Simons Road. As with those buildings, the applicant will also need to seek a height variance from the Zoning Board of Appeals for the new three-story building. With these changes the total unit count for the Willowbend project will be increased from 273 to 279 units, which is within the 287 units currently authorized under the Special Permit. All units will be connected to and served by the existing privately owned wastewater treatment plant which serves the entire Willowbend project.

Please feel free to contact me should you have any questions.

Sincerely yours

Jack MoÉlhinney, Attorney for Southworth Mashpee Properties LLC

cc: Town Clerk
Board of Health
Matthew Eddy, P.E.



Mashpee Planning Board Public Hearing Notice

Please be advised, if the Mashpee Town Hall is still closed to the public due to the COVID-19 public health emergency the public may participate in the following manner:

Virtual / Remote Meeting

Broadcast Live on Local Cable Channel 18

Call in Conference Number: (508) 539-1400 extension 8585

*Streamed Live on the Town of Mashpee Website:

https://www.mashpeema.gov/channel-18*

Pursuant to Massachusetts General Laws, Chapter 40A Section 11, the Mashpee Planning Board will hold a public hearing on Wednesday, July 1, 2020 at 7:10PM at the Mashpee Town Hall, 16 Great Neck Road North, to consider an application from Southworth Mashpee Properties LLC, property owner, to modify the Willowbend Country Club Special Permit. The applicant proposes to construct a 6-unit multifamily residential townhouse structure to be known as the Clubhouse Villas on a 40,009 square foot parcel located north of Quinaquisset Avenue and found on Assessors Map 69 Block 117. With these changes the total unit count for the Willowbend project would be increased to 279, which is within the 287 units currently authorized under the Special Permit. All units will be connected to and served by the existing privately owned wastewater treatment plant which serves the entire Willowbend project.

Submitted by:

Mary E. Waygan Mashpee Planning Board

Publication dates: Friday, June 12, 2020

Friday, June 19, 2020



Applicant:

Southworth Mashpee Properties LLC

Property Owner:

Southworth Mashpee Properties LLC

Subject Property:

Vacant parcel north of Quinaquisset Avenue Identified on plan recorded in Barnstable County Registry of Deeds Plan Book 657 Page 51 as Lot G-12A2 and on Mashpee Assessor's Map 69 Block 117

June 4, 2020

Dear Mashpee Property Owner,

As the registered owner of a property located within 300' of the subject property named above, you are being notified that the Mashpee Planning Board is holding a public hearing on <u>Wednesday</u>, <u>July 1</u>, <u>2020</u> at 7:10 PM in the Waquoit Meeting Room, Mashpee Town Hall, 1st Floor, 16 Great Neck Road North, <u>Mashpee</u>, <u>MA 02649</u> to solicit comments regarding the following case:

Southworth Mashpee Properties LLC has filed an application to modify the Willowbend Country Club Special Permit. The applicant proposes to construct a 6-unit multifamily residential townhouse structure to be known as the Clubhouse Villas on a 40,009 square foot parcel located north of Quinaquisset Avenue and found on Assessors Map 69 Block 117. With these changes the total unit count for the Willowbend project would be increased to 279, which is within the 287 units currently authorized under the Special Permit. All units will be connected to and served by the existing privately owned wastewater treatment plant which serves the entire Willowbend project.

Please be advised that the Mashpee Town Hall is still closed to the public due to the COVID-19 public health emergency and as such this meeting will be conducted virtually/remotely. The public may participate in the following manner:

- Broadcast Live on Local Cable Channel 18
- Call in Conference Number: (508) 539-1400 extension 8585
- Streamed Live on the Town of Mashpee Website: https://www.mashpeema.gov/channel-18*

If you wish to provide comment and are unable to call in to the conference line please submit comments to me in writing via the contact information provided below or by emailing the Planning Board at PlanningBoard@mashpeema.gov. Your comments will be entered into the public record for the Board's consideration.

Please do not hesitate to contact me by phone, email, or in person should you have questions about why you are receiving this notification.

Sincerely

Evan R. Lehrer, Town Planner 16 Great Neck Road North


Mashpee, MA 02649

elehrer@mashpeema.gov

(508) 539-1400 x. 8521

Clubhouse Villas At Willowbend Site Construction Plans

Mashpee, Massachusetts



Owner:

Southworth Cape Development, LLC 130 Willowbend Drive Mashpee, MA 02649 (508)-539-5316

Applicant:

Southworth Mashpee Properties, LLC 130 Willowbend Drive Mashpee, MA 02649 Phone (508)-539-5316

Engineer/Surveyor:

BAXTER NYE ENGINEERING & SURVEYING Registered Professional Engineers and Land Surveyors 78 North Street - 3rd Floor Hyannis, MA 02601 Phone (508) 771-7502 Fax - (508) 771-7622 ATTN: Matthew Eddy, P.E.

Job Number: 2014-009

PLAN SHEET INDEX

DRAWING TITLE

- 0.0 Cover Sheet
- 1.0 Legend and General Notes
- 2.0 Existing Conditions Plan
- 3.0 Layout and Dimension Plan
- 3.1 Tower Truck Turning Template Plan 3.2 Fire Engine Turning Template Plan
- 4.0 Grading and Drainage Plan
- 4.1 Stormwater Management Details and Notes

PREPARED FOR: SOUTHWORTH MASHPEE PROPERTIES, LLC 130 Willowbend Drive Mashpee MA 02549

BAXTER NYE **ENGINEERING &** SURVEYING

Registered Professional Engineers and Land Surveyors

78 North Street - 3rd Floor Hyannis, Massachusetts 02601

Phone - (508) 771-7502 Fax - (508) 771-7622

Willowbend Country Club Clubhouse Villas

		DATE	DESCRIPTION
SI	1 E E	T TITI	E

Cover Sheet

DATE: APRIL 14, 2020

OB NO: 2014-009 FILE: 2014-009-0UB RAS CYA

LECEND					
LEGEND EXIST PROP(BLACK T	ext represents "proposed" information)	EXSST	PROP(BLAC	x Text re	PRESENTS "PROPOSED" INFORMATION)
L=50.00°					
P	Roperty line Roject linit line			DRAINAGE OVERFLOY	
	KOJECT UMIT LINE IGHT-OF-WAY/PROPERTY LINE	-5*20	— ко —	ROOF DRA	
	ASSOCIAT	S	— s —	SEWER LI	
	UILDING SETBACK	CH19	онж	OVERHEAD	ELECTRIC, TELEPHONE & FIRE ALARM
 5	tate highway baseline	#	— w —	WATER LE	NE.
10±00 10±00 B	ASELINE	to	FP	FIRE PRO	TECTION LINE
	ONSTRUCTION LAYOUT	— ¢ —	G	gas une	
	ONING LINE	— 3 — — 3 — — — — — — — — — — — — — — —	E	UNDERGR	OUND ELECTRIC, DATA/COMMUNICATIONS LINES
	OWN LINE	т	<u> </u>	UNDERGR	OUND DATA & COMMUNICATION LINES
s	STATE LINE	FA	FA	FIRE ALA	RM
G	RAYEL ROAD		—F&P	FIRE & P	OLICE CABLE
500 500	DGE OF PAVEMENT		—-сату—	CABLE TV	1
<u>вс</u> <u>вс</u> в	etuminous curb	20 P.E	≅ ^{C8}	CATCH 8	asin (souare or round catch basin)
	CAPE COO BERNI	9528	EX0	DOUBLE	CATCH BASN
	RECAST CONC, CURB	and Same	DI DI	DRAM N	
see the	AERT, GRAN, CURB	ф 	==100 == ⊕ 0441	DRAIN MA	
	LOPED GRANL CURB	12.10m	an (Juss	TRENCH I	
,	SMIT OF CURBITYPE SANCUT	IES De	пз≽		oo End section
MATCH BE	ATCHLRE	\		HEADWAL	
		5		CONTROL	STRUCTURE
	SOUID WHITE LINE				
n/n	SOLID YELLOW LINE	P C	(S) 2MH	SEWER W	
***	Broken White Line	- 0	<u> </u>	GREASE	
	BROKEN YELLOW LINE	incir (B)	® grso	WATER M	
	SOLID WHITE CHANNELIZING LINE	§ ⋈	No.	WATER S	HUT OFF/CURS STOP ATE
ALC BY	SOLID YELLOW CHANNELIZING LINE		TSY		
	Double yellow une Stop une	*****			sleeve, valve, iser
	47%		€_		E REDUCER
	STEEL CUARD RAIL	⋄	Îwo	STAMESE FIRE HYD	CONNECTION
i e	MOOD GUARD RAIL	354	,#M	WATER M	
	STOCKADE FENCE	, Fr	PIY		XCATOR VALVE
	PATH	0	0	WELL	
	TREE LINE	-6-	-	MONITOR	ING WELL
l .	CHAIN LINK FENCE	Ġ	Ġ	RRIGATIO	ON CONTROL VALVE
·	STONE WALL RETAINING WALL	<u>%</u>	<u>×</u>	SPRINKU	ER HEAD
	HAY BALES	Q	õ	GAS GAT	
			CM	GAS MET	ER
2 1	MENOR CONTOUR	Œ.	Ø EMH		MANHOLE
	MAJOR CONTOUR	0	E	ELECTRO	
	TOP of SLOPE	ED	EM	ELECTRO	
	BOTTOM of SLOPE	♦	\$ ∢	FLOOD L	DLE (DECORATIVE)
		à	*		PE UGHT
	BUILDING	4-3	+1		LUMINAIRE
]dau]da	BUILDING DOOR	19-5-12			LUMINAIRE
]410]410	LOADING DOCK		-1-	TRIPLE	LUMINAIRE
]400] 400	OVERHEAD DOOR BOLLARD	19-4	- I -		LUMINAIRE
	DUMPSIER PAD			WALL F	ACK
	adı	CT.::::::::::::::::::::::::::::::::::::		SIGNAL	ARU
Fil PM	DOUBLE SIGN	20	0	MANHOL	
	PARKING METER	(←	UTIUTY	POLE/GUY MIRE
1 10	PARKING-COUNT	()()-	 -≎		POLE/GUY POLE
	COMPACT PARKING STALLS	3	⊕ ፷	PULL BO	
	CROSSWALK		6466		
***************************************	CROSSWALK				ce/haybale n bern/swale
(5:11E.)	CONC. PAVEMENT		#3	AH DIA	Y BALE CHECK DAM
	STANDARD DUTY FLEXIBLE PAYEMENT		A₽	POINT O	F INTERSECTION
	HEAVY DUTY FLEXIBLE PAYEMENT			FLARED	end Section (Fes) One protection
	HANDICAP RAMP				
<u> </u>	HANDICAP PARKING		6*P0	PERMET	ER DRAIN
£ &	VAN-ACCESSIBLE HANDICAP PARKING			PAVED 1	yaterway (pww) One protection
	CART CORRAL		•	mitt 21	WILL INTENTION
Detail no.			[;;;;;;;;;]	gire se	LY DA CWALF
on Sheet no.	DETAIL OR SECTION REFERENCE			AN IC MA	IT IN SWALE
Sheet not —		K.	:0#8	TREES	
4. 4.	WETLANDS	•	*150*	eun	
	50' WETLAND BUFFER		£3	SHRUB	
	100' WETLAND BUFFER	E:		OP	
	200' WETLAND BUFFER			LP.	LOW POINT
	UNIT OF WETLANDS			HP ∼o	HIGH POINT
-∆ ₅₂ - - ∆ ₅₂	WETLAND FLAG		,27,21 TC ,27,25 EE	QB _27.21 TOC 27.15 BOC	GRADE BREAK
	100 YEAR FLOOD PLAIN MITIGATION AREA LINE		27.15 BE 21.25	77.15 BOC 21.25	
	EDGE OF WATER		<	1+ 25	SPOT ELEVATION W/LEADER
				•	SPOT ELEVATION BORING LOCATION
0	TELEPHONE MANHOLE			ď.	TEST PIT LOCATION
× ×	TELEPHONE MARKER		»,÷ ■	₩	BENCH WARK
TS TS	TRAFFIC SIGNAL		•		THE IN TO EXISTING GRADE
© 5	SIGNAL BOX		COAY TENT		REPRESENTS EXISTING INFORMATION
	FIRE ALARM CONTROL PANEL		GRAY TEXT		
5 6	FIRE ALARM BOX		BLA	X TEXT	REPRESENTS PROPOSED INFORMATION
(E) (D	TRANSFORMER PAD				

ABBREVIATIONS ADJ ADJUST APPROXIMAT RETURNINGUS RETRA BITUMINOUS OURS BOTTOM OF SLOPE SOTTOM OF WALL COBBLESTONE EDGIN ECB EROSION CONTROL BLAKKET FIFY ELEVATION EXIST. **EXISTING** FOUNDATION FINISHED FLOOR ELEVATION CRADE BREAK GRANITE CURB GRANITE FEIGHG HANDICAP HIGH POINT LANDSCAPE AREA LOW POINT MAXMOM RESTAN WHR/FP IP WASS HIGHWAY ROUND/ ESCUTCHEON PIN I FAD PILIC NOT TO SCALE PRECAST CONCRETE CURB PROPOSTO PAYED WATER WAY REMOD REMODEL REMOVE REMOVE AND STACK RETAIN SLOPED GRANITE EDGING SLOPED GRANITE CURB TIE INTO EXISTING GRADI TOC TOP OF CURR TOP OF FOUNDATION TOP OF WALL TYPICAL UNLESS OTHERWISE NOTED VERSEY IN EIELD BY CONTRACTOR VCC VERTICAL CRANITE CURR UTILITY ASPHALT COATED CORRUGATED METAL PIPE CAP CORRUGATED ALLWAUM PRE CAST IRON PIPE CHANGE IN TYPE CORRUGATED METAL PIPE COND CONDUIT CPP HIGH DENSITY POLYETHYLENE CORRUGATED PLASTIC PIPE - SMOOTH INTEROR CURB STOP FOR WATER LINE mp NAME FOR DOC DOWN SPOUT ELECTRIC F&C FRAME AND COVER FRAME AND GRATE INTERCEPTOR DRAM INVERT ELEVATION PERFORATED DRAIN POLYWNYL CHLORIDE PIPE REINFORGED CONCRETE PIPE SEMER C/0 SEWER CLEANOUT 50 STORM DRAIN

TSY&B

WF

TAPPENG SLEEVE, VALVE & & BOX RISER

UTILITY POLE

WATER

VERBEY IN FIELD

GENERAL CONSTRUCTION NOTES

• (ALL REFERENCES TO "CONTRACTOR" SHALL MEAN THE GENERAL CONTRACTOR OR HIS SUB-CONTRACTORS.)

1. ALL WORK & MATERIALS SHALL BE IN ACCORDANCE WITH MASSDOT, HIGHWAY DIVISION, STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES (MASSDOT-SSHB), AS CURRENTLY AMENDED, UNLESS OTHERWISE NOTED. IF THERE ARE CONFLICTS IN ANY OF THE SPECIFICATIONS OR PROJECT DOCUMENTS, THE HIGHER STANDARD SHALL APPLY.

ALL WORK UNDER THESE DOCUMENTS SHALL ALSO CONFORM TO ALL CODES AND STANDARDS, AS CURRENTLY AMENDED, WHICH ARE APPLICABLE TO THIS PROJECT. ALL WORK SHALL FURTHER COMFORM TO SPECIFIC REQUIREMENTS, SPECIFICATIONS, ORDINANCES AND INTERPRETATIONS OF LOCAL AUTHORITIES HAVING JURISDICTION OVER THE PROJECT. DETERMINATION OF APPLICABLE CODES AND STANDARDS AND OF THE AUTHORITIES HAVING JURISDICTION, SHALL BE THE RESPONSIBILITY OF EACH CONTRACTOR, AS SHALL BE THE ANALYSIS OF ALL SUCH CODES AND STANDARDS IN REGARD TO THEIR APPLICABILITY TO THE PROJECT FOR SECURING ALL APPROVALS AND PERMITS.

ALL WORK WITHIN THESE PLANS SHALL BE PERFORMED AND PROVIDED BY THE CONTRACTOR IN ACCORDANCE WITH THE CONSTRUCTION DETAILS PROVIDED IN THIS PLAN SET WHETHER OR NOT THE DETAIL NUMBER IS SPECIFICALLY REFERENCE.

EXCEPT WHERE THE PROJECT DOCUMENTS INCLUDE MORE STRINGENT REQUIREMENTS, APPLICABLE CONSTRUCTION INDUSTRY STANDARDS HAVE THE SAME FORCE AND EFFECT AS IF BOUND HERETO. SUCH STANDARDS ARE MADE A PART OF THE PROJECT DOCUMENTS BY

2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL QUANTITY ESTIMATES AND VERIFTING, TO HIS OWN SATISFACTION, THAT ALL QUANTITIES ARE ACCURATE FOR ALL CONSTRUCTION MATERIAS, INCLUDING CUT & FILL ESTIMATES WHICH THE CONTRACTOR MAY PREPARE BASED ON INFORMATION CONTAINED WITHIN THESE PLANS.

3. WHERE AN EXISTING UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, THE LOCATION, ELEVATION AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY THE CONTRACTOR, AND THE INFORMATION FURNISHED TO THE ENGINEER FOR RESOLUTION OF THE CONFLICT.

4. THE CONTRACTOR SHALL MAKE ALL ARRANGEMENTS WITH THE APPROPRIATE UTILITY COMPANIES FOR OBTAINING CONSTRUCTION PERMITS AND PERFORMING ALL NEW CONSTRUCTION, RELOCATION, ALTERATION AND ADJUSTMENT OF GAS, ELECTRIC (INCLUDING UTILITY POLES), TELEPHONE, CABLE, FIRE ALARM, WATER, SANITARY SEWER, STORM DRAIN, AND ANY OTHER UTILITIES, BOTH PUBLIC AND PRIVATE, AS REQUIRED.

5. THE LOCATION OF EXISTING UNDERGROUND SYSTEMS, INFRASTRUCTURE, UTILITIES, CONDUITS, WELLS, AND LINES ARE SHOWN IN AN APPROXIMATE WAY ONLY, MAY NOT BE LIMITED TO THOSE SHOWN HEREIN, AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER, THE ENGINEER, OR THEIR REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION, BOTH HORIZONTALLY AND VERTICALLY, OF ALL ESTISTING UTILITIES, CONDUITS, LINES, WELLS, AND OTHER BURIED INFRASTRUCTURE AND SYSTEMS BEFORE THE START OF ANY WORK. THE CONTRACTOR AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL ANY YORK. THE CONTINGUOUS ARREES TO BE POLLT RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTINACTOR'S FALURE TO LOCATE THE INFRASTRUCTURE AUTULITIES, CONDUITS AND LINES EXACTLY. THE CONTRACTOR SHALL PRESERVE ALL UNDERGOUND INFRASTRUCTURE AND UTILITIES AS REQUIRED. THE CONTRACTOR MUST CALL "DIG SAYE" (AT 1-888-DIG-SAFE) AT LEAST 72 HOURS BEFORE THE START OF CONSTRUCTION.

8. THE CONTRACTOR SHALL BE RESPONSIBLE TO CALL AT LEAST 24 HOURS AHEAD FOR INSPECTIONS BY THE APPROPRIATE AUTHORITY IN ACCORDANCE WITH THE TOWN REQUIREMENTS, AS APPLICABLE.

7. THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES, PUBLIC AND PRIVATE, INCLUDING THOSE IN CONTROL OF UTILITIES NOT SHOWN ON THIS PLAN, (SEE CHAPTER 370, ACTS OF 1963, MASSACHUSETTS) PRIOR TO COMMENCING ANY WORK.

9. THE TERM "PROPOSED" (PROP.) MEANS WORK TO BE CONSTRUCTED USING NEW MATERIALS OR, WHERE APPLICABLE, RE-USING EXISTING MATERIALS IDENTIFIED AS "REMOVE AND RESET" (Rar).

11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THAT THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS DO NOT CONFLICT WITH ANY KNOWN EXISTING INFORMATION OR OTHER PROPOSED IMPROVEMENTS. IF ANY CONFLICTS ARE DISCOVERED, THE CONTRACTOR MUST NOTIFY THE OWNER OR ENGINEER IMMEDIATELY UPON DISCOVERY AND AT LEAST 72 HOURS PRIOR TO INSTALLATION OF ANY PORTION OF THE AFFECTED WORK.

12. THE CONTRACTOR SHALL REFER TO ARCHITECTURAL AND STRUCTURAL DRAWINGS FOR ALL BUILDING DIMENSIONS AND CONSTRUCTION. BUILDING DIMENSIONS SHOWN HEREIN ARE FOR COORDINATION WITH OTHER SITE WORK ONLY AND SHOULD NOT BE USED TO STRUCTURE OUT BUILDING. SITE CONTRACTOR SHALL STAKE OUT THE EXTERIOR BUILDING CORNERS FROM THE LATEST ARCHITECTURAL PLANS. THE CONTRACTOR SHALL NOTIFY BAXTER NYE ENGINEERING & SURVEYING OF ANY DISCREPANCIES BETWEEN SITE PLAN DIMENSIONS AND ARCHITECTURAL BUILDING PLANS BEFORE PROCEEDING WITH ANY PORTION OF SITE WORK WHICH MAY BE EFFECTED SO THAT PROPER ADJUSTMENTS TO THE SITE LAYOUT CAN BE MADE IF NECESSARY.

13. PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL SUBMIT A SCHEDULE OF OPERATIONS TO THE OWNER AND ITS REPRESENTATIVE. THE CONTRACTOR SHALL NOTIFY AND COORDINATE WITH THE OWNER, ITS ENGINEER OR REPRESENTATIVE.

14. THE CONTRACTOR SHALL CONTACT THE ENGINEER TO SCHEDULE A PRE-CONSTRUCTION MEETING AT LEAST TWO (2) WEEKS PRIOR TO COMMENCING CONSTRUCTION.

15. THE CONTRACTOR SHALL MAKE SUBMITTALS TO THE ENGINEER FOR APPROVAL BEFORE ANY FABRICATION OR DELIVERY OF PRODUCTS OR MATERIALS.

16. CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR JOB SITE SAFETY AND ALL CONSTRUCTION MEANS AND METHODS. BAXTER NYE ENGINEERING & SURVEYING, DOES NOT ASSUME ANY RESPONSIBILITY IN JOB SITE SAFETY FOR CONSTRUCTION METHODS USED. ALL FEDERAL, STATE, AND LOCAL OSHA REQUIREMENTS AND REGULATIONS SHALL BE FOLLOWED BY ALL PERSONNEL ON THE JOB SITE AT ALL TIMES.

17. THE CONTRACTOR SHALL REMOVE ALL STUMPS, RUBBISH, AND DEBRIS FROM THE PROJECT SITE. STORAGE OF THESE TIEMS WILL NOT BE PERMITTED ON THE PROJECT SITE. THE CONTRACTOR SHALL LEAVE THE SITE IN A SAFE, CLEAN, AND LEVEL CONDITION AT THE COMPLETION OF THE SITE CLEARANCE WORK.

18. ALL UNSUITABLE MATERIALS ENCOUNTERED WITHIN THE LIMIT OF WORK SUB GRADES SHALL BE REMOYED, AS DIRECTED BY THE ENGINEER OR OWNERS REPRESENTATIVE, TO NATURAL STABLE GROUND BY THE CONTRACTOR. UNSUITABLE MATERIALS INCLUDE TOPSOIL, LOAM, PEAT, ALL ORGANIC MATERIAL, SNOW, ICE, CONSTRUCTION RUBBLE, TRASH, AND OTHER DELETERIOUS DEBRIS.

19. TREES AND SHRUBS WITHIN THE LIMITS OF GRADING SHALL BE REMOVED AND RESET ONLY UPON APPROVAL OF THE ENGINEER OR OWNERS REPRESENTATIVE.

20, AREAS OUTSIDE THE LIMITS OF PROPOSED WORK DISTURBED BY THE CONTRACTOR'S OPERATIONS, WITHOUT PRIOR APPROVAL BY THE OWNER OR ITS REPRESENTANTE, SHALL BE RESTORED BY THE CONTRACTOR TO THEIR ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE.

21. EXISTING SUBSURFACE ROCK IS NOT SHOWN ON THE PLANS. IT SHALL BE THE RESPONSIBILITY OF THE CONTINCTOR TO MAKE THEIR OWN DETERMINATION AS TO THE LOCATION OF SUBSURFACE ROCK.

22. THE CONTRACTOR SHALL PROTECT ALL UNDERGROUND DRAINAGE, SEWER, AND UTILITY FACILITIES FROM EXCESSIVE VEHICULAR LOADS DURING CONSTRUCTION, ANY FACILITIES DAMAGED BY CONSTRUCTION LOADS SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S EXPENSE.

23. ALL EXISTING SIGNS WITHIN THE PROJECT LIMITS SHALL BE RETAINED UNLESS NOTED

24. JOINTS BETWEEN NEW BITUMINOUS CONCRETE ROADWAY PAVEMENT AND SAWCUT EXISTING PAVEMENT SHALL BE SAMED WITH BITUMEN AND BACKSANDED, ALL JOINTS TO EXISTING PAVEMENT SHALL BE SAWCUT TRUE AND STRAIGHT. ALL CRACKED OR INADEQUATE PAVEMENT AND/OR SUBBASE MATERIAL SHALL BE REMOVED AND REPLACED.

25. ALL PROPOSED WALKWAYS WILL BE HANDICAPPED ACCESSIBLE. ALL PROPOSED SLOPES ON WALKWAYS SHALL BE LESS THAN 5% AND ALL CROSS SLOPES < 2%. THESE ARE MAXIMUM SLOPES WITH NO TOLERANCE. ALL WORK WILL BE IN ACCORDANCE WITH THE MOST CURRENT REQUIREMENTS OF THE U.S. ACCESS BOARD, AMERICANS WITH DISABILITIES ACT & COMMONWEALTH OF MASSACHUSETTS, ARCHITECTURAL ACCESS BOARD.

26. FINAL LAYOUT AND STAKING OF ALL PROPOSED FEATURES AND GRADING SHALL BE REVIEWED IN THE FIELD AND APPROVED BY THE OWNERS REPRESENTATIVE PRIOR TO ANY SITE PREPARATION OF CONSTRUCTION. THE CONTRACTOR SHALL NOT ADJUST OR MODIFY THE LAYOUT AND STAKING OF ANY PROPOSED FEATURES WITHOUT FINAL APPROVAL FROM THE CHAMERS REPRESENTATIVE AND ANY GOVERNMENTAL AGENCY WHICH MAY HAVE JURISDICTION OVER CONTEMPLATED CHANGE.

27. ALL ELECTRICAL (BOTH PRIMARY AND SECONDARY), TELEPHONE, DATA/COM AND FIRE DEPARTMENT CONDUITS AND APPURTEMANT FEATURES REQUIRED by THE APPLICABLE UTILITY COMPANY ARE TO BE INSTALLED BY THE ELECTRICAL CONTRACTOR. TRENCHING, BACKFILLING, CONCRETE WORK, MANHOLE AND RELATED STRUCTURES. AND STREET REPAIR SHALL BE PERFORMED BY THE GENERAL CONTRACTOR/SITE CONTRACTOR. ALL ASSOCIATED COSTS FOR COMPLETE EXECUTION OF THIS WORK SHALL BE INCLUDED IN THE CONTRACTORS PRICING.

28. RIM ELEVATIONS OF DRAINAGE AND SANITARY SEWER MANHOLES ARE APPROXIMATE, FINAL ELEVATIONS ARE TO BE SET FLUSH AND CONSISTENT WITH GRADING PLANS, ADJUST ALL OTHER RIM ELEVATIONS OF MANHOLES, GAS GATES, WATER GATES AND OTHER UTILITIES TO FINISHED GRADE WITHIN THE LIMITS OF THE SITE WORK.

29, ALL AREAS DISTURBED DURING CONSTRUCTION SHALL BE REPLACED IN KIND. SURFACES NOT OTHERWISE TREATED SHALL BE STABILIZED AS LAWNS. ALL LAWN AREAS SHALL HAVE A MODIFIED LOAM BORROW PLACED, SEEDED, FERTILIZED, LIMED AND MULCHED UNTIL GRASS STAND IS ESTABLISHED AND SURFACE IS STABILIZED. THE MODIFIED LOAM BORROW SHALL JUNIOU DE CHARLISTEU AND SURFACE, IS SIABILIZEU, HHE MODIFIED LOAM BURKOUW SHALL HAVE A MINIMUM DEPTH OF 6" AND SHALL BE PLACED FLUSH WITH THE TOP OF ADJACENT CURB, ECGING, BERM, OR OTHER SURFACE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RAEAS UNTIL VEGETATION HAS BEEN PERMANENTLY ESTABLISHED. SLOPES IN EXCESS OF 31 SHALL BE FURTHER STABILIZED WITH EROSION CONTROL BLANKETS (ECB) OF CURLEX OR

30. THE CONTRACTOR SHALL WATER, MOW, FERTILIZE OR OTHERWISE MAINTAIN ALL SODDED AND SEEDED OR OTHERWISE STRAILIZED ARRES UNTIL GRASS STANDS OR OTHER VEGETATED METHODS ARE ESTABLISHED TO THE SANSFACTION OF THE OWNER OR THEIR REPRESENTATIVE.

31. THE CONTRACTOR SHALL RESET ALL MONUMENTATION DISTURBED DURING CONSTRUCTION AT NO ADDITIONAL COST TO THE OWNER. THE CONTRACTOR SHALL PROVIDE A SURVEY BY A PLS TO ENSURE THAT THE MONUMENTATION IS RESET TO ITS ORIGINAL LOCATION, MONUMENTS INCLUDE, BUT ARE NOT LIMITED TO, TOWN BOUNDS, MASS HIGHWAY BOUNDS, PROPERTY LINE MONUMENTS, IRON RODS, STAKES, CONCRETE BOUNDS, GRAHITE BOUNDS AND STONE WALLS WITH DRILL HOLES.

EXCAVATION SAFETY:

ALL EXCAVATION MUST FOLLOW OSHA, MASSACHUSETTS AND LOCAL REGULATIONS FOR SAFETY. ALL TRENCH EXCAVATION EXCEEDING 3 FEET OF DEPTH WILL REQUIRE A TRENCH PERMIT FROM THE LOCAL TOWN OR CITY PRIOR TO ANY EXCAVATION.

DRAWINGS STATEMENT

THE CONTRACTOR WILL PREPARE AS-BUILT DRAWINGS, STAMPED BY A MA LICENSED PROFESSIONAL ENGINEER (PE) CERTIFFING THAT: TO THE EBST OF THEIR KNOWLEDGE, JUDGEMENT AND BELLEF, THE CONSTRUCTED WORK IS IN GENERAL CONFORMANCE WITH THE

INSPECTIONS:

1. CONTRACTOR SHALL COORDINATE WITH THE ENGINEER ON ALL NECESSARY INSPECTIONS AT THE PRE-CONSTRUCTION MEETING. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AT LEAST 48 HOURS (2 BUSINESS DAYS) AHEAD OF A REQUIRED INSPECTIONS.

2. AT A MINIMUM, THE FOLLOWING INSPECTIONS WILL BE REQUIRED:
A. INSTALLATION OF SEDIMENT AND EROSION CONTROLS AT LIMIT OF WORK PRIOR TO COMMENCING CONSTRUCTION.

B. BOTTOM OF EXCAVATION FOR EACH STORMWATER MANAGEMENT (SWM) FACILITY.
C. FINAL STABILIZATION AND PLANTINGS PRIOR TO REMOVING ANY SEDIMENT AND

- FINE ADMINISTRATION AND MANTINGS PRIOR TO REMOVING ANY SEDIMENT AND EROSION CONTROL DEVICES.

D. BN WILL NEED TO WITNESS A REPRESENTATIVE UTILITY INSTALLATION BEFORE BACKFILL FOR:

- WATER

- TMALE.

CONTRACTOR TO PROVIDE BN WITH WATER DEPT. APPROVED INSPECTION
REPORT

- SCWER
CONTRACTOR TO PROVIDE BN WITH SEWER DEPT. APPROVED INSPECTION
REPORT

REPORT

E. GRAVEL BORROW SUBBASE UNDER ALL PAVED AND CONCRETE SURFACES (UNLESS OTHERWISE WITNESSED BY A TESTING AGENCY.)

F. BN WILL NEED TO WITNESS REPRESENTATIVE INSTALLATION OF VERTICAL CURBING.

G. BN SHALL BE PROVIDED FOR REVIEW, ALL TESTING AGENCY LABORATORY MATERIAL.

AND ON-SITE TESTING RESULTS AS REQUIRED UNDER THE PROJECT DOCUMENTS FOR COMPLETE REQUIREMENTS, INCLUDING BUT NOT LIMITED TO:

— SANIDY TOPSOIL SIEVE ANALYSIS AND MATERIAL CHARACTERISTICS PER SPEC
— ALL COMPACTION TESTING RESULTS FOR BEACKFILL.

— GRAVEL BORROW MATERIAL UNDER PANING, SIDEWALK, SITE SLABS, PADS, ETC., AS TO DEPTH OF MATERIAL PLACEMENT AND COMPACTION TESTING RESULTS.

— BITUMINOUS CONCRETE PLACEMENT AND COMPACTION TESTING RESULTS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING MATERIAL SAMPLES TO AND COORDINATING WITH THE TESTING AGENCY AS REQUIRED.

BAXTER NYE

BAXTER NYE **ENGINEERING &** SURVEYING

Registered Professional Engineers and Land Surveyors

78 North Street - 3rd Floor Hyannis, Massachusetts 02601

Phone - (508) 771-7502 Fax - (508) 771-7622

STAMP	SIAMI

CONSULTAN

CONSULTANT

PREPARED FOR SOUTHWORTH MASHPEE PROPERTIES, LLC

130 Willowbend Drive

Mashpee MA 02549

PROJECT TITLE Willowbend Country Club Clubhouse Villas

		DATE	DESCRIPTION			
9.1	SHEET TITLE					

Legend and **General Notes**

C1.0

DATE: APRIL 14, 2020

DRAWN BY:SOM CHECKED BY:MINE

FOR PERMIT ONLY - NOT FOR CONSTRUCTION

Œ

2


TR

TELEPHONE RISER


MAIL BOX

JOB NO:2014-009

FILE:2014-009-CLUB LG.dwg



D14Z01+G06Z1VILVLG1ZLUB NGGN-VIIARZ01+G0R bean PDF, 1:1



ZONING TABLE

ZONING DISTRICT: R-3 (Residential) OVERLAY DISTRICTS: Non

ALLOWED USE: RESIDENTIAL

EXIST USE: RESIDENTIAL, VACANT PROPOSED USE: RESIDENTIAL MULTI-FAMILY

6 UNIT (LARGE TOWNHOUSE UNITS x 1 BLDGS = 6 UNITS

TOTAL NUMBER OF UNITS

TOTAL PARCEL AREA: 394,208± SF, 9.05	± AC (LOT A - LOT B + I	OT C)
	REQUIRED/ALLOWED (R3)	PROVIDED/PROPOSED
MIN. LOT AREA	40,000	40,009 SF
FRONTAGE	150 FT	167.88 FT.
PERIMETER SETBACK	50 FT	138.40 FT
MAX. BLDG, HEIGHT (STORIES)	2 STORIES/35 FT.	*3 STORIES -39 FT
MAX. % LOT COVERAGE (STRUCTURES) TOTAL PARCEL: 40,009± S.F.	20% (8,002± S.F.)	12% (4,786± SF)
PARKING TABLE		
RESIDENTIAL 2 PER UNIT (6 X 2 =12)	12 SPACES	12 PRKG, SPACES
TOTAL PARKING		12 SPACES
DESIGN VEHICLE		AASHTO SU

^{*}VARIANCE REQUIRED

NOTES:

- 1. ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH MHDSS, TOWN ORDINANCES, REQUIREMENTS, AND SPECIFICATIONS.
- 2. THE CONTRACTOR SHALL CONTACT THE ENGINEER TO SCHEDULE A PRE-CONSTRUCTION MEETING AT LEAST TWO (2) WEEKS PRIOR TO COMMENCING CONSTRUCTION.
- 3. THE CONTRACTOR SHALL MAKE SUBMITTALS TO THE ENGINEER FOR APPROVAL BEFORE ANY FABRICATION OR DELIVERY OF PRODUCTS OR MATERIALS.
- 4. ALL PROPOSED WALKWAYS WILL BE HANDICAPPED ACCESSIBLE. ALL PROPOSED RUNNING SLOPES ON WALKWAYS SHALL BE LESS THAN 5% AND ALL CROSS SLOPES < 2%. THESE ARE MAXIMUM SLOPES WITH NO TOLEPANCE. ALL WORK WILL BE IN ACCORDANCE WITH THE MOST CURRENT REQUIREMENTS OF THE U.S. ACCESS BOARD, AMERICANS WITH DISABILITIES ACT & COMMONWEALTH OF MASSACHUSETTS, ARCHITECTURAL ACCESS BOARD.
- 5. EXISTING PAYING EDGES SHALL BE SAWCUT TO CREATE A CLEAN EDGE WHERE IT IS TO BE TIED INTO NEW PAYING, OR WHERE ASPHALT IS REMOVED ADJACENT TO ASPHALT WHICH IS TO REMAIN. BROKEN OR UNSTABLE PAVEMENT SHALL BE REMOVED AND SUBBASE REPLACED WITH SUITABLE COMPACTED MATERIAL PER PAYEMENT SECTION DETAIL HEREIN. ANY SAWCUT LINES SHOWN ON THE PLANS ARE APPROXIMATE ONLY. THE EXACT EDGE OF SAWCUT SHALL BE DETERMINED BY THE CONTRACTOR IN THE FIELD TO PROPERLY BLEND TO THE SURROUNDING GRADES. PROPOSED ASPHALT SHALL BE PROPERLY BUTTED AND BLENDED TO SURROUNDING ASPHALT WHICH IS TO REMAIN. THE BILENDED TRANSITION BETWEEN PROPOSED AND EXISTING ASPHALT SHALL BE WITH AN APPROXIMATE 1.5% GRADE UNLESS OTHERWISE IDENTIFIED. THE JOINT SHALL NOT BE ABRUPT.
- 6. DIMENSIONS SHOWN ARE TO OUTSIDE FACE OF FOUNDATION OR FACE OF CURB WHERE
- 7. ALL PAVEMENT MARKINGS AND STRIPING SHALL FOLLOW MUTCD STANDARDS. TYPICAL LINE WIDTH FOR LANE AND PARKING STALL STRIPING SHALL BE 4 INCHES UNLESS OTHERWISE NOTED. PARKING STALL COLOR SHALL BE WHITE, TYPICAL, UNLESS OTHERWISE NOTED.
- 8. BUILDING AND SITE SIGNAGE SHALL MEET REQUIREMENTS OF TOWN ZONING AND/OR SIGN
- 9. SITE LIGHTING SEE ELECTRICAL DRAWINGS IN ARCHITECTURAL PLAN PACKAGE FOR DETAILED INFORMATION.

SIGN SUMMARY				
M.U.T.C.D.	SPECIFICATION		TEXT	QUANTITY
NUMBER	MDTH	HEIGHT	IEAI	CUANTITI
нс•	12*	18*	SEE LOCAL	1
			REQUIREMENTS (YAN)	

SIGN INSTALLER SHALL COORDINATE SPECIFIC SIGN INFORMATION AND WORDING REQUIREMENTS WITH LOCAL AGENCIES AS NECESSARY.

ALL SIGNAGE MUST BE IN CONFORMANCE WITH THE FEDERAL HIGHWAY ADMINISTRATION "MANUAL ON UNIFORM TRAFFIC CONTROL DEMOCS" (MUTCO), LATEST EDITION, ALL APPLICABLE CODES, AND LOCAL REQUIREMENTS, LOCAL REQUIREMENTS, WHEN THEY EXIST, SHALL SUPERCEDE MUTCO.

BAXTER NYE **ENGINEERING &** SURVEYING

Registered Professional Engineers and Land Surveyors

78 North Street - 3rd Floor Hyannis, Massachusetts 02601

Phone - (508) 771-7502 Fax - (508) 771-7622 www.baxter-nye.com

> STAMP STAMP

CONSULTANT

CONSULTANT

PREPARED FOR: SOUTHWORTH MASHPEE PROPERTIES, LLC 130 Willowbend Drive

Willowbend Country Club Clubhouse Villas

Mashpee MA 02549

П					
	T	DATE	DESCRIPTION		
-	CHEET TITLE				

Layout &

Dimension Plan


C3.0

DATE - APRIL 14, 2020

SCALE IN FEET SCALE: 1"=20"

OB NO: 2014-009

* ADD "VAN ACCESSIBLE" WHERE APPROPRIATE
* COLOR AND WORDING PER LOCAL
REQUIREMENTS





SURVEYING Registered Professional Engineers and Land Surveyors

78 North Street — 3rd Floor Hyannis, Massachusetts 02601

Phone - (508) 771-7502 Fax - (508) 771-7622 www.baxter-nye.com

STAMP STAMP CONSULTANT

CONSULTANT

PREPARED FOR: SOUTHWORTH MASHPEE PROPERTIES, LLC 130 Willowbend Drive Mashpee MA 02549

PROJECT TITLE Willowbend Country Club Clubhouse Villas

DATE DESCRIPTION Tower Truck

Turning Template Plan

C3.1


30 0 30 60


SCALE IN FEET
SCALE: 1"=30"

DRAWN BY: 50M CHECKED BY: MWE

FOR PERMIT ONLY - NOT FOR CONSTRUCTION

Mostpee Fire Truck





BAXTER NYE **ENGINEERING &** SURVEYING

Registered Professional Engineers and Land Surveyors

78 North Street — 3rd Floor Hyannis, Massachusetts 02601

Phone - (508) 771-7502 Fax - (508) 771-7622 www.baxter-nye.com

CONSULTANT

CONSULTANT

STAMP

PREPARED FOR: SOUTHWORTH MASHPEE PROPERTIES, LLC 130 Willowbend Drive Mashpee MA 02549

PROJECT TITLE
Willowbend Country Club
Clubhouse Villas

DATE DESCRIPTION

Fire Engine Turning Template Plan

C3.1

DATE: APRIL 14, 2020 -



BASIN BOTTOM SHALL BE 3 INCHES SANDY YOPSOIL INFETRATBLE SUBGRADE SHALL BE "MAINTAINED," IF FILL IS NEEDED FOR SUBGRADE BELOW THE BASIN BOTTOM, FILL MATERIAL SHALL BE PER MHD—SSIB MI.04,0, TYPE B. > BOTTOM OF INFILTRATION AREA EL=16.5 118.2 $\overline{\infty}$ SWM FACILITY DETAIL

SCALE IN FEET

GRADING AND DRAINAGE NOTES

- 2. DISTURBED AREAS SHALL BE PROTECTED AT ALL TIMES TO CONTROL SEDIMENT TRANSPORT BEYOND THE LIMIT OF WORK.
- 3 DISTURBED AREAS SHALL BE TREATED WITH WATER BURING EXCAVATION, OR APPROVED ALTERNATIVE, TO CONTROL THE DUST.
- 4. THE STE SUBCONTRACTOR SHALL PROVIDE ALL EXCAVATION, BACKFILL AND COMPACTION NECESSARY TO ADSENCE THE RINSH GRADES SHOWN ON THE PLANS AND FOR INSTALLATION OF BUILDING STRUCTURES, PANNIG, STORMWATER MANAGEMENT AND ALL UNLITIES (INTERIOR AND EXTERIOR). SITE CONTRACTOR TO REFER TO SITE ELECTRICAL, MEP AND LIANDSCAPE PLANS FOR ADDITIONAL INFORMATION OF THE PLANS AND EVALU.

5. ALL PIPE OUTFALLS, CURB OPENINGS, STOKE MERS, CHECK DAMS, AND OTHER DRAINAGE OVERFLOW AND OUTET AREAS SHALL HAVE RIPRAP EXTENSED FROM THE OUTLET TO THE BOTTOM OF SLOPE WITH A MINIMUM TO IT X TO IT RIPRAP LEVEL SPREADER, UNLESS OTHERMISE SPECIFICALLY DETAILED, ALL STONE OUTFALLS SHALL BE PROPERLY SHAPED SO THE RUNOFF IS CONTAINED WITH THE STONE LINING. SEE THYROLD GETLAIS FOR ADDITIONAL INFORMATIONAL INFORMATIONAL INFORMATION.

7. ALL DRAINAGE PIPING SHALL BE DESIGNED AND INSTALLED FOR H-20 LOADING.

8. A 25' MINBULM SEPARATION SHALL BE MAINTAINED BETWEEN ALL STORM WATER WANGEMENT INFLITRATION FACULTIES AND SANTARY SEMER/SEPTIC DISPOSAL AREAS AND HAZARDOUS STORAGE TARKS/FACULTIES. IO FEET MINBULM SEPARATION SHALL BE MAINTAINED BETWEEN ALL STORM WATER MANGEMENT INFLITRATION FACULTIES AND SANTARY SEMER/SEPTIC DIRES, MAINTAINED BETWEEN ALL STORM WATER MANGEMENT INFLITRATION FACULTIES AND SANTARY SEMER/SEPTIC DIRES, MAINTAINED BETWEEN ALL STORM WATER MANGEMENT INFLITRATION FACULTIES AND SANTARY SEMER/SEPTIC DIRES, MAINTAINED BETWEEN ALL STORM WATER MANGEMENT INFLITRATION FACULTIES AND SANTARY SEMER/SEPTIC DIRES, MAINTAINED BETWEEN ALL STORM WATER MANGEMENT INFLITRATION FACULTIES AND SANTARY SEMER/SEPTIC DIRES, MAINTAINED BETWEEN ALL STORM WATER MANGEMENT INFLITRATION FACULTIES AND SANTARY SEMER/SEPTIC DIRES, MAINTAINED BETWEEN ALL STORM WATER MANGEMENT INFLITRATION FACULTIES AND SANTARY SEMER/SEPTIC DIRES, MAINTAINED BETWEEN ALL STORM WATER MANGEMENT INFLITRATION FACULTIES AND SANTARY SEMER/SEPTIC DIRES, MAINTAINED BETWEEN ALL STORM WATER MANGEMENT INFLITRATION FACULTIES AND SANTARY SEMER/SEPTIC DIRES, MAINTAINED BETWEEN ALL STORM WATER MANGEMENT INFLITRATION FACULTIES AND SANTARY SEMER/SEPTIC DIRECTOR TO THE SANTARY SEMER SANTARY SEM

9. CONTRACTOR TO YERFY IN FIELD, WITH ENGNEER PRESENT, SOIL INFERTATION RATE AND GROUNDWATER ELEVATION PRIOR TO ORDERING OF MATERIALS OR COMMENCEMENT OF CONSTRUCTION (ASSUMED 8.27 INCHES/HR. INFERTATION RATE). IF RATE VARIES FROM ASSUMPTION OR GROUNDWATER IS PRESENT, SYSTEM MAY HAVE TO BE REDESCRED AS DETERMINED BY THE ENGINEER, MAY MATERIALS ORDER OR CONSTRUCTION COMMENCED PRORE TO THIS CONTRIVENT OF THE CONTRACTORS OWN RISK.

UNSUITABLE MATERIALS ENCOUNTERED ADJACENT TO SOIL INFILTRATION LAYERS SHALL BE REMOVED FOR 5 FT AROUND THE LEACHING SYSTEMS/FACILITIES AND REPLACED WITH SAND MALDIAN TYPE B.

12. ALL PIPE INSTALLATIONS SHALL FOLLOW PROJECT SPECIFICATIONS AND PIPE MANUFACTURER RECOMMENDATIONS.

13. AL GRADING WORK SHALL BE DONE IN A WORKMANINE MANIER ACCOMPLISHED TO CREATE POSTINE DRINNAGE AND ELIBINATE ANY PUDDLING OR PONDING. WHERE NOT OTHERWISE NOTED OR DEPINED ON THE PLAN, ALL CUT AND FILL SHALL BE RELEGED TO DANIAGHT AT EXISTING GROVE WITH A 3.1 SLOPE.

THE CONTRACTOR SHALL NOTIFY THE ENGINEER WITH ANY GRADE ISSUES OR QUESTIONS PRIOR TO PERFORMING THE FINISH GRADING WORK

IB REVEAL IS TO BE 6 INCHES (FOR VERTICAL FACE) UNLESS OTHERRISE NOTED BY TOP OF CURB (FOC) AND BOTTOM OF CURB (BOC) ELEVATIONS. WHERE THESE ARE NOTED THE ALL REVIEW TO PROVIDE REQUERED REVIEWS AND THAT PROPERTY TAPER THE CURB AND FINISH GRADE BACK TO THE THYPICAL B WICH REVIEW. IF TOO OR BOC LIBELS ARE NOT SHOWN, ALL S ARE BOTTOM OF CURB WHICH ADJURCENT TO A CORB FACE.

18. BOTTOM OF WALL (BON) OR TOP OF WALL (TOW) LEVATIONS FOR RETAINING WALLS NOTED ON THE PLAN ARE APPROXIMATE ELEVATIONS WHERE THE WALL IS EXPECTED TO DAYLOHT WITH EXISTING GRADE. STRUCTURAL RETAINING WALL DESIGN IS DONE BY OTHERS AND THE BOY OR TOW EXISTING GRADING LEVATIONS FOR WHITE THE WALL HOURD DAYLOHT TO EXISTING GRADES SHALL BE WEREED AS THE STRUCTURAL DESIGN. THE ACTUAL BOW OR TOW ELEVATION AT THE PROPOSED WALL(S) MAY DEFINE FROM CONTROLS SHOWN ON THE PLANS ESPECIALLY AT TESTED SLOPES ARE STRUCTURAL DOWN OF TOWN ELEVATION AT THE PROPOSED WALL(S) MAY DEFINE FROM CONTROLS SHOWN ON THE PLANS ESPECIALLY AT TESTED SLOPES ARE SHOWN OF THE PLANS ALL BE PROTECTED FROM SEDIMENT AND SLITATION STALL THESE, JUST PRIOR TO COMPLETION, THE STE SUBSCONTRACTOR SHALL PERFORM A FINAL INSPECTION AND CLEANING OF THE STOWN WATER MARKEGUENT STRIPM. ALL SEDMENT AND SLITATION SHALL BE REJOYED FROM THE BUSINES. FIC. AND THESE AREAS SHALL BE SHAPED TO FINAL CONTROLS AND ELEVATION, PER IN PLANS CALL BE WALLE SK DESSENT TO THE SHAPE AND FROM THE BUSINES.

17. ANY DEMATERING OPERATION WHEN REQUIRED AS PART OF THE CONSTRUCTION PROCESS SHALL ENSURE ALL DEMATERING OCCURS THROUGH A PROPER DEMATERING BASIN (STONE, FILTER FABRIC AND HAMBALES OR OTHER ACCOPTABLE MEANS) PRIOR TO DISCHARGE FROM THE STE.

18. ALL WORK WINKIN THESE PLAYS SHALL BE PERFORMED AND PROVIDED BY THE CONTRACTOR IN ACCORDANCE WITH THE CONSTRUCTION DETAILS PROVIDED IN THIS PLAY SET WHETHER OR NOT THE DETAIL NOWINER IS SPECIFICALLY REFERENCED.

EXCAVATION/FILL NOTES:

I. SDE SLOPES OF TRENCH EXCANDINGS DEEPER THAN 4 FEET SHOULD BE FLATTENED AS REQUIRED BY SIT CONDITIONS TO AT LEAST LINLY OR SUPPORTED WITH TRENCH BOX OR SANLAR DEVICE, ALL MORK SHALL BE PERFORMED SAFELY AND IN ACCORPOACE WITH TOSAL AND MOSH REQUIREDHIS, CONTINCTORY AND LIGHTAN TRENCH PERMIT AS REQUIRED.

2. AFTER REMOVAL OF TOPSOIL AND RUDGOUNTE MATERIALS, GENERAL FILL SUBGRADE SHOULD BE PROOF—ROLLED WITH A LONGED 10—WHEEL TANDED—AXIE DUMP TRUCK. THE PROOF—ROLLING SHOULD BE PROOFED AS PRICEDED BY A GETTICHNOCAL EXCHETE, NO FILL SHOULD BE PRACED WITH THE SUBGRADE IS PREVIOUS BY A GETTICHNOCAL EXCHETE, BORROW MATERIALS FOR FILL OPERATIONS FOR GETTICHNOCAL SHOWNERS, AND EXCHANGE SHOULD BE CONSTRUCTED IN 8° LOOSE WITS AND COMPACTED AS POLLOWS, UNLESS GIVEN HOTED BY PROJECT SPECTATIONS.

PILLS SUPPORTING FORMANDERS, AND FLOOR SALES, SANK SKY AND THIS STATEMENT OF THE STATEMENT OF TH

OPERATION/MAINTENANCE PLAN

1. THIS OPERATION AND MAINTENANCE PLAN SHALL BE PERFORMED BY THE GENERAL CONTRACTOR DURING CONSTRUCTION OPERATIONS AND BY THE OWNER ONCE THE FACULTIES ARE COMPLETED AND PUT INTO OPERATION.

2. PERSONNEL ASSOCIATED WITH THE CONSTRUCTION OF THIS PROJECT SHALL BE INFORMED THAT THE MAINTENANCE OF SETATION CONTROLS TAKES PRECEDENCE OVER NORMAL CONSTRUCTION ACTIVITIES. ADMICINITY PROPERTIES AND STREETS SHALL BE PROJECTED FROM ENGINED ON SUITATION CONTINUES.

4. ACCUMULATED DEBRS IN CATCH BASINS, WATER QUALITY BILETS, OL/WATER SEPARATORS AND LEACHING BASINS SHALL BE REMOVED BEFORE IT EXCEEDS 12 INCHES IN DEPTH AND DISPOSED OF PROPERLY, BROKEN OR DAMAGED CAS TRAPS/HOODS SHALL BE INMEDIATELY REPARED OR REPLACED TO ENSURE ADEQUATE FUNCTION.

5. A YSUAL INSPECTION SHALL BE MADE AT ALL DRAMAGE CHANNELS FOR THE ENTIRE STORM DRAMAGE SYSTEM. THE GENERAL CONDITION OF THESE SYSTEMS SHOULD BE REVIEWED AND ACCUMULATED DEBBS SHALL BE REMOVED. THE CONDITION OF ALL CURLETS SHALL BE NOTED AND A DESCRIPTION OF THE DRAMAGE SYSTEMS SHALL BE NOLIDED IN THE REPORT, DELETEROUS MATERIALS SHALL BE REMOVED FROM THE DRAMAGE CHANNELS IN ORDER FOR THE SYSTEM TO RUNCHOOL PROPERTY.

6. ALL OUTLETS, DRAWING CHANNELS, AND SLOPES SHALL BE KEPT STABILIZED. ANY EROSION SHALL BE REPAIRED IMMEDIATELY,

7. ACCUMULATED SEDMENT SHALL BE REMOVED FROM THE SMM BASIN BEFORE IT EXCEEDS 1' IN DEPTH, OR AT LEAST ONCE EVERY 5 YEARS. THE LOW FLOW OUTLET SHALL BE CLEANED AND INSPECTED FOR PROPER PUNCTIONING. ALL DEBMIS OR DELETENOUS MATERIAL SHALL BE REMOVED, BASIN SLOPES SHALL BE MANITAINED MITH A GRASS STAND OF AT LEAST 3". GRASS SHALL BE MOWED AT LEAST THICK A TEXAN AND CUPPINGS SHALL NOT BE LEFT IN BASIN. ANY THESE OR OTHER MOODY VECTATION GROWING A BUDGHIST OR REAR CONTROL STRUCTURE SHALL BE ROUGHED. AND CONTROL STRUCTURE SHALL BE ROUGHED.

THE FOLLOWING MANAULU INFORMATION SHALL BE RECORDED;
 OATE OF INSPECTION
 OGEREAL CONDITION OF THE ENTIRE SYSTEM
 OGERECTIVE MAINTENANCE ACTIONS TAXON TO ENSURE ADEQUATE FUNCTION AND WHEN PERFORMED.
 A COPY OF THESE INSPECTION REPORTS SHALL BE FURNISHED TO THE PLANNING BOARD UPON REQUEST.

9, MANTENANCE OF THE STORMARTE MANAGEMENT FACULTY SHALL BE IN ACCORDANCE WITH THE EXECUTED INSPECTION AND MANTENANCE AGREEMENT FOR PRIVATE STORMWATER MANAGEMENT FACULTIES AND SHALL BE THE RESPONSIBILITY OF THE OWNER AND THE ASSOCIATES.

OL THE CONTRACTOR MUST NOTIFY THE BUILDING DEPARTMENT AND THE PLANNING BOARD ENGINEER AT LEAST THO (2) DAYS PRIOR TO THE START OF CONSTRUCTION

CONSTRUCTION SEQUENCE

- 1. INSTALL SILT FENCING/HAY BALES TO ESTABLISH THE LIMIT OF WORK AS SHOWN ON PLAN.
- 2. CONSTRUCT TEMPORARY CONSTRUCTION ENTRANCES AT POINTS OF EGRESS FROM THE SITE DURING CONSTRUCTION.
- GES FROM DEWATERING OF EXCAVATIONS SHALL NOT BE DIVERTED DIRECTLY INTO ANY WETLANDS OR EXISTING STORM DRAINS WITHOUT PRETREATMENT MA SETTLING BASINS.
- 5. CLEAR AND GRUB SITE WITHIN THE LIMIT OF WORK.

BOS

BOTTON OF SLOPE

BOTTON OF WALL

GRADE BREAK

HIGH POINT

LOW POINT

TOP OF CURS

FINISHED FLOOR ELEVATION

- 6. CONSTRUCT SYM BASIN TO WITHIN 1 FT OF FINAL BOTTOM ELEVATION, BASIN TO BE USED AS SEDMENT TRAP
- 7. ESTABLISH ROUGH SUB GRADES FOR PARKING LOT AND BUILDING PLATFORM. B. PERFORM BUILDING AND SITE CONSTRUCTION, INSTALL BASE COURSE PAYING AS SOON AS PRACTICAL.
- 9. INSPECT AND MAINTAIN EROSION CONTROL MEASURES AFTER RAINFALL EVENTS AND A MINIMUM OF ONCE PER WEEK.
- 10. REMOVE SECUMENT BUILDUP AT EROSION CONTROL DEVICES AS NEEDED, REDISTRIBUTE MATERIAL OVER SITE IN CONFORMANCE WITH EARTHWORK SPECIFICATION
- 11. CNCE ALL DRAINGE STRUCTURES ARE INSTALLED, INSTALL FILTER FABRIC AND STONE OR HAY BALES AROUND ALL HEM STRUCTURES AND MAINTAIN THEM UNTIL PAYEMENT IS IN PLACE AND VEGETATION IS ESTABLISHED. ALL OUT FALLS SHALL BE STABLUZED MITH STONE PROTECTION AS REQUIRED.
- 12. ALL DIT AND FILL SLOPES SHALL BE TEMPORARLY STABUZED WITH TOP SOLL, SEED AND MULCH OR CURRELY AS REQUIRED IF CONSTRUCTION ACTIVITY CEASES ON SAID SLOPES FOR A PERSOD OF 14 DATE OF GREATER, ALL SLOPES SHALL BE PERMANENTLY STABUZED AS REQUIRED MEDITIATELY UPON COMPLETION OF PRIAL GRADURE.
- 13, PROVIDE SILT FENCE FOR INFILTRATION PROTECTION, INFILTRATION AREAS SHALL BE PROTECTED AT ALL TIMES FROM CONSTRUCTION TRAFFIC AND SEDIMENT DURING CONSTRUCTION
- 14. COMPLETE FINISH GRADING AND STABILIZATION OF SITE. PLACE FINAL PAYING COURSE.

BAXTER NYE **ENGINEERING &** SURVEYING

Registered Professional Engineers and Land Surveyors

78 North Street - 3rd Floor

Phone - (508) 771-7502 Fax - (508) 771-7622 www.baxter-nye.com

STAMP

CONSULTANT

CONSULTANT

PREPARED FOR: SOUTHWORTH MASHPEE PROPERTIES, LLC 130 Willowbend Drive Mashpee MA 02549

PROJECT TITLE

Willowbend Country Club Clubhouse Villas

		DATE	DESCRIPTION
SHEET TITLE			

Grading & **Drainage Plan Notes & Details**

C4.0

DATE: APRIL 05, 2020

SCALE IN FEET SCALE: 1"=20"

FOR PERMIT ONLY - NOT FOR CONSTRUCTION

OB NO: 2014-009

SWM SPECIFICATIONS

ALL MATERIALS AND WORK SHALL BE IN ACCORDANCE WITH THE MASSDOT/MASSHIGHMAY STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRODGES (MHDSS), SPECIFIC ON-SITE SOIL SPECIFICATIONS IF A GEOTEGORICAL REPORTS WAS PERFORANCE, AND THE PLANS HEREIN. WHERE CONFLICTS OF INFORMATION EXIST, THE MORE RESTRICTIVE SHALL APPLY. ALL REFERENCES TO ASTM AND AASHTO SPECIFICATIONS AND PROVINCE RECYST VICTOR RECESSION VICTOR RECESSION VICTOR RECESSION VICTOR RECESSION VICTOR RECESSION VICTOR RECESSION VICTOR RECEIVED VICTOR VI

(NOTE: THE CONTRACTOR SHALL BE RESPONSIBLE TO FALLY UNDERSTAND, THIS INFORMATION AND INTENT OF THE SMM FACILITIES AND SHALL REVIEW THIS INFORMATION WITH THE ENGREER AS NEEDED. SITE PREPARATION AND GRADING:

AREAS DESCHATED FOR BORROW AREAS, EMBANGENT, AND STRUCTURAL WORKS SHALL BE CLEARD, GRUBBED AND STREPFED OF TOPSOL. ALL TREES, VEGETATION, ROOTS AND OTHER OR EXCHANGE F MATTHAL SHALL BE REVOICED. CHANGEL BANKS AND SHAPP BERKALL BE AREA FOR THAN 15.1.

AREAS TO BE CONDICED BY THE INTERTACION AFEA. BASH OR RESERVOR MAL BE CLEARD OF ALL TREES, BRUNDAN LOSS, FEMORES, RUBBIN AND OTHER OBSECTIONABLE MATERIAL LINESS OTHERWIS DESIGNATED OF THE FLAUS. THESE, BRUNDAN OF SUMPER SHALL BE CLEARED. ALL CLEARED AND GRUBBED MATERIAL SHALL BE OSPOSED OF OUTSIDE AND BELOW THE LIMITS OF THE DAW, BASH AND RESERVOR AS DECEDED BY THE OWNER OF HIS BERTERSHATANCE.

THE CONTRACTOR SHALL ENSURE ALL SMM AREAS WHICH ARE DESCRIED FOR INFLITATION SHALL HAVE THEIR EXISTING INFLITATIORS SUBSOIL CONDITIONS UNCHANGED AT THE HEREIN SPECIFIED FROM THE DESCRIED FOR THE DESCRIED FOR THE DESCRIED FROM THE DESCRIED FOR THE DESCRIED FROM THE DESCRIPT FROM THE

TOPSOL OR PLANTING MATERIAL REQUIRED FOR SEEDING, SOO OR VEGETATION GROWTH ON THE BASIN BOTTOM AND NON-EMBANGMENT SCESLOPES, SHALL BE PLACED IN ONLY A THREE (3) INCH SURFACE OPERIN OF LOAMY SAND OR SANDY LOAM TOPSOL (EXCESSIVE TOPSOL SHALL NOT BE PLACED WHERE INFILITATION IS USED). THE TOPSOL SHALL BE LESS THAM SK CALLY CONTENT (MON CSTAN SEASON) FROM STANDING FOR SON SENCY, CORRECTED PH 45.—45. AND ORGANIC MATERIA OF BETWEEN LAST TO 3X.

THREE (3) INCHES OF HARDWOOD WILCH SMALL BE PLACED AROUND REQUIRED SHRUBS AND OTHER SPECIFIED LANDSCAPE PLANTINGS, MULCH SMALL BE PLACED AROUND FEB BOTTOM OF BIO-RETENTION AREAS IF SPECIFIED IN THE PLAN DETAILS. THERE A PLANTING PLAN OR SCHEDULE IS NOT IDENTIFIED FOR THE SMAI FACULTIES, THEN THE BOTTOM AND SIDE SLOPES OF SMM BASINS AND BIORETENING FACULTIES WILL BE STRABULED AND SECEDE AS FOLLOWS.

BOTTOM OF BUSINS/ACUTES SHALL BE SEEDED AND STREETED MIN "HEN PRICAMD CONSERVATION" AND MUDIES SEED MA".

- DECE CLOPES SHALL BE SEEDED AND STREETED MIN "HIN" PRICAMD DESIGNED CONTROC, PRESTORATION SEED MAX".

- HE CONTRACTOR SHALL BE RESPONSIBLE FOR REPARANG EROSON, CLEANOUT OF SEDMENT FROM EROSON, AND RESEDENCY AS NEEDED UNTIL FULL STABUZATION IS ACREVED. THIS SHALL BE RECORDED TRONG SEASONS.

NO OTHER MATERIALS UNLESS SPECIFICALLY IDENTIFIED AND REVIEWED BY THE ENGINEER, SHALL BE PLACED ON THE BASIN BOTTOM

EARTH FILL FOR EMBANKMENTS ONLY:

MATERIAL — THE FILL MATERIAL SHALL BE TAKEN FROM APPROVED DESIGNATED BORROW AREAS. IT SHALL BE FREE OF ROOTS, STUMPS, WOOD, RUBBISH, STONES GREATER THAN 6°, FROZEN OR OTHER ORSECTIONABLE MATERIALS. FILL MATERIAL FOR THE CENTER OF THE DAY EMPARKMENT AND CUT OFF TRENCH WHICH ARE TO BE IMPERIALSHED SHALL CONFIDENT TO HELD STANLARD IT DESIGN AND CONSTRUCTION ARE STONES OF THE ORDER OF THE DESIGNATION FOR CONSTRUCTION ARE STONES OF THE ORDER OF THE DESIGNATION FOR CONSTRUCTION ARE STONES OF THE ORDER OF THE DESIGNATION FOR CONSTRUCTION ARE STONES.

PLACEMENT - AREAS ON WHICH FILL IS TO BE PLACED SHALL BE SCARFIED PRIOR TO PLACEMENT OF FILL. FILL MATERIALS SHALL BE PLACED IN MAXIMUM 8 INCH THICK (BEFORE COMPACTION) LAYERS AND ARE TO BE COMPINIOUS OVER THE ENTINE LEGISM OF THE FILL. THE MOST PERMEABLE BORROW MATERIAL SHALL BE PLACED IN THE DOWNSTREAM PORTIONS OF THE DAM EMBANAUM PROPRIES OF THE DAM EMBANAUM PROPRIES OF THE MOST PROPRIES OF THE MAXIMUM PROPRIES OF THE DAM EMBANAUM PROPRIES OF THE MAXIMUM PROPRIES OF THE DAM EMBANAUM PROPRIES OF THE MAXIMUM PROPRIES OF THE DAM EMBANAUM PROPRIES OF THE MAXIMUM PROPRIES OF TH

COMPACION — THE MOMENTY OF THE MURROL WID STREAMS EQUIPMENT OFFIT THE EMPANDENT FILL SHALL BE CONTROLLED SO THAT THE ENTIRE SHEFFOCT OF CACH LET SHALL BE TRAVERSED BY NOT LESS THAN ONE THEAD THEATHAND OF THE COMPACION OF SEX STANDARD PROCTOR SHALL BE ADMENTED. SHALL CONTROL SHALL BOUNDAIN SHALL CONTROL SHAPE SHOT SHALL CONTROL SHAPE SHOT SHAPE SHOT SHAPE OF COMPACION OF SEX STANDARD PROCTOR SHALL BE ADMENTED. THE MATERIAL SHALL CONTROL SHAPE SHAP

BACKELL ADJACENT TO PDES OR STRUCTURES SHALL BE OF THE TYPE AND QUALITY CONFORMING TO THAT SPECIFIED FOR THE ADJOINING FILL MATERIAL. THE FILL SHALL BE PLACED IN MORIZONTAL LAYERS NOT TO EXCEED FOUR WHOLES IN TROCKESS AND COMPACTED BY HAND TAMPENS OR OTHER MANUALLY DIRECTED COMPACTION ECOMPACTION COMPACTION FOR AND ADJACENT OT THE MATERIAL NEEDS TO FILL COMPACTED VILLESS THERE IS A COMPACTED FILL OF 24" OR GREATER OVER THE STRUCTURE OF PPE.

ROCK RIPRAP SHALL MEET THE REQUIREMENTS OF MINDSS.

THE RIPRIAP SHALL BE PLACED TO THE REQUIRED THEORESS IN ONE OPERATION. THE ROCK SHALL BE DELIVERED AND PLACED IN A MAINER THAT WILL INSURE THAT THE RIPRIAP IN PLACE SHALL BE REASONABLY HOMOGRAPOUS WITH THE LARGER ROCKS INFROMED AND PRINCY IN CONTROL TO A NOTHER WITH THE SHALLER ROCKS FILLING THE VOIDS BETWEEN THE LARGER ROCKS. FILTER CLOTH SHALL BE PLACED UNDER ALL REPARAD MOS SHALL REPET THE REQUIREDHERTS OF MODES.

PIPE CONDUITS

ALL PIPES SHALL BE CIRCULAR IN CROSS SECTION.

REINFORCED CONCRETE PIPE-

ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR REINFORCED CONCRETE PIPE:

1, MATERIALS — REINFORCED CONCRETE PIPE SHALL HAVE BELL AND SPIGOT JOHTS WITH RUBBER CASKETS AND SHALL EQUIA, OR EXCEED ASTM C-361, THIS BEDDING SHALL CONSST OF HIGH SLUMP CONCRETE PLACED UNDER THE PIPE AND UP THE SDES OF THE PIPE AT LEAST 10% OF 175 QUISIOE CHAMETER WITH A MINIMUM THICKNESS OF J NICHES, OR AS SHOWN ON THE DRAWNICS. 2. BEDOING - ALL REINFORCED CONCRETE PIPE CONDUITS SHALL BE LAID IN A CONCRETE BEDOING FOR THEIR ENTIRE LENGTH,

4. BACKFILLING SHALL CONFORM TO "STRUCTURE BACKFILL".

5. OTHER DETAILS (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWNOS.

POLYVINYL CHLORIDE (PVC) PIPE-

1. MATERIALS - PVC PIPE SHALL BE PVC-1120 OR PVC-1220 CONFORMING TO ASTM D-1785 OR ASTM D-2241.

2. JOINTS AND CONNECTIONS TO ANTI-SEEP COLLARS SHALL BE COMPLETELY WATERTIGHT.

3. BEDDING - THE PPE SHALL BE FIRMLY AND UNFORMLY BEDDED THROUGHOUT ITS DITIRE LENGTH. WHERE ROCK OR SOFT, SPONGY OR OTHER UNSTABLE SOIL IS ENCOUNTERED, ALL SUCH MATERIAL SHALL BE REDUKED MIN SUTHER EARTH COMPACTION FOR DECIDING ADMICENTAL SHAPEN. 4. BACKFILLING SHALL CONFORM TO "STRUCTURE BACKFILL".

5. OTHER DETAILS (ANTI-SEEP COLLARS, VALVES, ETC.) SHALL BE AS SHOWN ON THE DRAWINGS

CONCRETE SHALL MEET THE REQUIREMENTS OF MHOSS.

ROCK RIPRAP ROCK RIPRAP SHALL MEET THE REQUIREMENTS OF MINDSS.

THE RIPRAP SHALL BE PLACED TO THE RECURED THICKNESS IN ONE OPERATION. THE ROCK SHALL BE DELIVERED AND PLACED IN A MANNER THAT MILL RISIRE THE RIPRAP IN PLACE SHALL BE REASONABLY MOUDOSPECOUS MITH THE LARGER ROCKS UNFORMLY DISTRIBUTED AND FRANCY IN CONTACT ONE TO ANOTHER MITH THE SHALLER ROCKS FILLING THE VOIDS BETWEEN THE LARGER ROCKS. FILLING THE VOIDS BETWEEN THE LARGER ROCKS.

IOM FLOW COPING (FEDERINED ON I.A.M. AS NEGLED).

PERFORMAND PREFOR LANDIN MINER ASAN TO USERIEMA SOE TOE OF OVERLOW SLOPE, AND NON-PERFORATED PPC AS NEEDED TO EXTEND UNDER OVERFLOW WOR TO CUTLET, EXTEND CLANGUT PPCS TO SURFACE WITH WONED CAPS AT TIES AND WICES.
ANY CLANGUT PPCS TO SURFACE WITH WONED CAPS AT TIES AND WICES.
ANY CLANGUT PPCS TO SURFACE WITH WONED CAPS AT TIES AND WICES.
ANY CLANGUTS IN AREA SUBJECT TO VEHICLAN LONDING SIALL SE INSTALLED WITH CONCRETE COLLARS.

CARE OF WATER DURING CONSTRUCTION

ALL BORROW AREAS SHALL BE GRADED TO PROVIDE PROPER DRAINAGE AND LEFT IN A SIGNITY CONDITION. ALL EXPOSED SUFFACES OF THE EMBANAGEM, SPILLMAY, SPOL AND BORROW AREAS, AND BERUS SHALL BE STABILIZED BY SEEDING, LURKING EMBANAGEM, AND INLORDER IN ACCORDANCE WITH MINISTER STABILIZED BY SEEDING, LURKING EMBANAGEM.

CONSTRUCTION OPERATIONS WILL BE CARRIED OUT IN SUCH A MANNER THAT EROSON WILL BE CONTROLLED AND WATER AND AR POLLUTION MINIMIZED. STATE AND LOCAL LAWS CONCERNING POLLUTION ABATEMENT WILL BE FOLLOWED. DETAIL ENGOGN AND SEDMENT CONTROL MEASURES TO BE EMPLOYED DURNING THE CONSTRUCTION PROCESS SHALL BE IN ACCORDANCE WITH THE SEDMENT EROSON CONTROL PLAN HERBERN AND CEREBRALLY ACCEPTED PRACTICES.

STORMARTER MANAGEMENT FACULTIES SMALL BE PROTECTED FROM SEDMENT AND SITATION AT ALL TIMES, JUST PROR TO COMPLETION, THE SITE SUBCONTRACTOR SMALL PERFORM A FINAL INSPECTION AND CLEMENT OF THE STORM FOR THE MANNEY FORBERTS, ETC. ON THESE AREAS SMALL BE SWAPED TO FINAL CONTROLLS AND ELEVATION FOR THE PLANS ALL REPORTS SMALL BE WAPED TO FINAL CONTROLLS AND ELEVATION FOR THE PLANS ALL REPORTS SMALL BE WAPED AND EXCHANGE FROM TO PLANS HAVE THE PLANS ALL REPORTS SMALL BE WAPED TO FINAL THE PLANS ALL REPORTS AND THE PLANS AND THE PLANS ALL REPORTS AND THE PLANS AN CORRUGATED METAL PIPE

ALL OF THE FOLLOWING CRITERIA SHALL APPLY FOR CORRUGATED WETAL PIPE:

I. MATERIAS — (STEEL PRE) — THE PRE AND ITS APPRITCHANCES SHALL BE CALVANEED AND FILLY BITLINGUIS COATED AND SHALL COURSEN NO THE REQUIREMENTS OF ASSIST SECTION.

—160 THER A MINI MATERIAGE COURTING BANDS. ANY BITLINGUIS COATRIO DANGED OR OTHERWISE SHAVED SHALL BE REPLACED WITH COLOR APPLIED BITLINGUIS COATRING COMPOING. STEEL PRESS WITH POLICIEST COATRING SHALL HAVE A MEMBAUL COATRING THE COLOR BAND APPROVED EQUAL MAY BE USED.

REXM, PLAST-COTE, BLOC-ALVA, AND BETH-O-LOY. COATRID CORRIGATED STEEL PRES SHALL BEET THE REQUIREMENT OF ASSIST MASSIST, AND M-248.

MATERIALS - (ALUMRIUM COATED STEE, PIPE) - THIS FIPE AND ITS APPURTDANCES SHALL CONFORM TO PILE RECURREMENTS OF AGAING SPECIFICATION M-274 WITH MATERITISM COUPLING BANDS OF PILES ENGINEED AND AUDITION COMPOUND.

3. CONNECTIONS — ALL CONNECTIONS WITH PIPES MUST BE COMPLETELY HANGERIGHT. THE DRAIN PIPE OR BARREL CONNECTION TO THE RISER SHADED ALL ADOING WHEN THE PIPE AND RISER ARE WELTAL ANTI-SEEP SHALL BE CONNECTED TO THE PIPE AN SICH A MARKER AS TO BE COMPLE WATERTIGHT. OMEPTE BANGS ARE NOT CONSIDERED TO BE WATERTIGHT.

WATERIORT, DUPLE BANDS ARE NOT CONSIDERED TO BE WATERIORY.

ALL CONNECTIONS SHALL USE A RUBBERO ON INCOEMPIC GASCET WHEN KORNON PIPE SCHOOKS. THE END OF EACH PIPE SHALL BE RE-ROLLED AM ADEQUATE HINDERS OF CORNINGATIONS TO ACCOMMODATE HE BAND WORL. THE FOLLOWING TIPE CONNECTIONS ARE ACCEPTABLE FOR PIPES LESS THAN 24" IN DIAMETER: FLANCES ON BOTH DIPS OF THE PIPE, A 12" WOE STANDAR LUP TIPE BAND WITH 12" MODE BY 3/8" THICK CUSSED CELL CRICILLAR RECOPRETE GASCET, AND A 12" WOE BY 3/8" THICK CUSSED CELL CRICILLAR RECOPRETE GASCET, AND A 12" WOE STANDARD A MIRRIAM DAMETER OF 1/2" GEALER THAN THE CORNICATED BY A 2" LONG ANNIAL OR CORNICATED BHAN USING ROSS SHALL BE CONNECTED BY A 2" LONG ANNIAL ORGORIZATION BUSING ROSS AND LUGS. A 12" WOE BY 3/6" THICK CLOSED CELL CORDICATE DEACH RECOPICE CASCET MALL BE ASSELLED ON THE EITH OF EACH PIPE FOR A TOTAL OF SANCET.

INSPECTIONS:

SHALL NOTIFY THE ENGINEER AT LEAST 48 HOURS AHEAD OF REQUIRED HISPECTIONS.

2. AT A MARKUM, THE FOLLOWING INSPECTIONS WILL BE REQUIRED:
A. HISTALLATION OF SEDMENT AND EROSION CONTROLS AT LIMIT OF WORK PRIOR TO COMMERCIAL CONSTRUCTION.

FAULUIT.

C. AT COMPLETION OF INSTALLATION OF EACH SYM FACULTY PRIOR TO BACKFILL.

BAOSTIL

D. DURNO INSTALLATION OF THE BIO-INFILITATION/RETENTION SECTIONS AS APPLICABLE

APPLICABLE

NOTE: THE CONTROL OF SHALL TOPSOIL LAYER AND TREOMESS RISTALLED.

NOTE: THE CONTRACTOR SHALL WERE ARROWS THAT LEVEL AND TREOMESS TO FINE CONTROL THE CONTRACTOR SHALL DESCRIPTION AND PROVIDED TO FINE CRANING, RISTALLIAL DIOC OF PLANTINGS AND SEASURABILIZATION, AND FLATTINGS PRIOR TO REJOVENG ANY SEDIMENT AND PLANTINGS PRIOR TO REJOVENG ANY SEDIMENT AND ERGON CONTROL DENGES.

AS-BUILTS:

OVER FLOW SPELWAY STONE SHALL BE FER VHD-SSHB WZ.02.3

TRACTOR WILL CAUSE TO BE PREPARED AS-BUILT DRAWINGS OF THE SIMI REM(S), STAMPED BY A MA LICENSED PROFESSIONAL ENGINEER (PE) CERTIFYING "" TO THE BEST OF THER KNOWLEDCE, JUDGINIT AND BELIFT IN THE INSTALLED STAMPATER MAINACEMENT SYSTEM(S) MEET(S) THE DESIGN DETAILS, STACKAINS, VOLUMES AND DESIGN ELEVATIONS.

BAXTER NYE ENGINEERING & SURVEYING Registered Professional Engineers and Land Surveyors 78 North Street - 3rd Floor Phone - (508) 771-7502 Fax - (508) 771-7622 www.baxter-nye.com STAMP STAMP CONSULTANT CONSULTANT PREPARED FOR SOUTHWORTH MASHPEE PROPERTIES, LLC 130 Willowbend Drive Mashpee MA 02549 PROJECT TITLE Willowbend Country Club Clubhouse Villas

DATE DESCRIPTION

Stormwater Management **Details & Notes**

C4.1

DATE: APRIL 14, 2020 SCALE IN FEET SCALE: 1"=20"

GRASS SWALE DETAIL

Section 1 PROFILE VIEW Existing swale grade Reth to ray from three times the pipe former if pipe collet (17 Inc.) to if it is more time for a seets (5 FT UNLESS GHERRIE WOLLD (N PLAN) MOTES:

1. Store to be set level if discharging to natural drainage.

2. Store to conform to stope when statisticing cut on fill stope per plan. Battorn of store strall be fairlied and level at both and store to the fairlied and level at both and store to the fairlied and level at both and store to the fairlied and level at both and store for min. Storens of 10 fit, unless otherwise nature. the plan.

I. Stone to be per M2.02.3

4. See Plan sheets for pipe specifications. RIP-RAP OULET PROTECTION I N.T.S. DETAIL


100

4" SCH 40 PYC SOUD OUTLET PIPE. GROUND WATER ELEV.=14.4 V SECTION THROUGH SPILLWAY 4 INCH SURFACE DEPTH OF LOAMY SAY IEXTURE, WITH LESS THAN 5% CLAY CONTENT, CORRECTED PH 5.5-6.5, AND ORGANIC WATTER OF BETWEEN 1.5% TO 3% THE TOPSOL SHALL HAVE AN INFILTRATION RATE OF 2.5 IN/HR. POND BOTTOM ELEV.=16.5 SEED VIX SHALL BE ERNST SEEDS
"RETENTION BASIN FLOOR MIX - LOW
MAINTENANCE" SEED VIX OR EQUAL WITH
STORMWATER AND FOREBAY SURFACES. MAINTAIN INFILTRATABLE SOILS SECTION THROUGH STORAGE PARALLEL TO SPILLWAY 3:1 SIDE SLOPES-6" CRUSHED STONE WHEN PROPERTY OF THE PARTY OF T SECTION THROUGH SPILLWAY INFILTRATION POND SECTIONS DETAIL

PCOLD BOTTOM ELEV.=16.5 D=1.5 X WAX STONE DIAWETER, SUT NOT LESS THAN 12

TOP OF BERM

FOR PERMIT ONLY - NOT FOR CONSTRUCTION



UTILITY NOTES.

2. 12" MINIMUM VERTICAL CLEARANCE SHALL BE MAINTAINED BETWEEN ALL UTILITY CROSSINGS.

3. A MINIMUM TO HORIZONTAL SEPARATION SHALL BE MANTANED BETWEEN WATER AND SEWER LINES, WHERE WATER LINES CROSS SEWER LINES, THE SEWER LINE SHALL BE LOCATED WITH A MINIMUM VERTICAL CLEARANCE OF 16' BELOW THE WATER LINE. THE SEWER LINE JOINTS SHALL BE LOCATED EQUIDISTANT AND AS FAR AWAY FROM THE WATER LINE AND SEWER LINE

4. SCHER MAINS TO BE 8" MIN. SDR-35 PVC WITH A MIN. SLOPE OF 0.50% UNLESS OTHERMSE NOTED. SEWER MAINS AND SEWER FORCE MAINS TYPICAL COVER OVER SEWER LINE SHALL BE 6". IF LESS THAN 4" OF COVER IS PROVIDED, INSULATE SEWER LINE AGAINST FREEZING IN ACCORDANCE WITH DETAIL \$205 OR EQUAL.

5. SEWER BUILDING CONNECTIONS SHALL BE 4" MIN. SCHEDULE 40 PVC, U.O.N., AT A MIN. SLOPE OF 1.0% U.O.N. A CLEANOUT SHALL BE SET ON EACH SERVICE LINE AT A DISTANC OF 10" +/- (U.O.N.) OFF THE FOUNDATION. ALL PIPPING FOR COMMERCIAL BUILDINGS SHALL BE PER PLUMBING CODE WITHIN 10 FEET OF BUILDING.

6. WATER MAINS TO BE CEMENT LINED DUCTILE IRON PIPE CLASS 52, U.O.N. ALL CONSTRUCTION METHODS AND MATERIALS SHALL BE AS REQUIRED BY, AND IN ACCORDANCE WITH THE LOCAL WATER DEPARTMENT AND APPLICABLE ANWAS SECONCATIONS.

10. ELECTRIC, DATA/COM IS SHOWN SCHEMATICALLY HEREON. ALL LABOR, WORK, EQUIPMENT AND MATERIALS FOR INSTALLATION OF THESE UTILITIES SHALL BE OWNED AND PERFORMED BY THE CONTRACTOR. UTILITIES SHALL BE INSTALLED WITH A MINIAUM COVER OF 5 FEET U.O.M. OR OTHERWISE DIRECTED BY THE CONTROLLING UTILITY COMPANY. CONTRACTOR SHALL COORDINATE ALL FRAIL LAYOUTS AND DETAILS WITH APPLICABLE UTILITY CAMPANY.

11. EXTERIOR RESIDENTIAL LIGHTING SHALL BE LOW WATTAGE TYPE AND DIRECTED SO AS TO KEEP ALL LIGHTING WITHIN SUBJECT LOT, ANY SITE LIGHTING USED SHALL BE LOW WATTAGE STREET LANTERIS ON 15' MADJULIN POLE LOCATED ADJACENT TO SUBJECT LOT DRIVEWAY, PARKING OR WALLKHAYS.

12. ALL UTILITY CUTS THROUGH EXISTING CONCRETE OR BITUMINOUS CONCRETE PAVED SURFACES SHALL BE SAND. BACK FILLING OF TRENCH SHALL INCLUDE 12" IN DEPTH FLOWABLE FILL TO THE BASE COURSE OF THE SURFACE TREATMENT. THE SURFACE TREATMENT SHALL THEN BE REPLACED IN MIND. IF THE BITUMINOUS CONCRETE SURFACE IS WITHIN THE ROADWAY, THE BITUMINOUS CONCRETE TOP COURSE SHALL BE FINISHED WITH INFRARED TREATMENT TO BLEND EXISTING AND NEMLY PAVED SURFACES, IF REQUIRED BY THE MUNICIPALITY.

13. SITE CONTRACTOR TO OWN ALL EXCAVATION, TRENCHING, & BACKFILLING FOR ALL UTILITIES AND MISCELLANEOUS WORK INCIDENTAL TO THE SCOPE OF THE PROJECT AND CONTRACT DOCUMENTS. CONTRACTOR SHALL REFER TO MEP AND LANGSCAPE PLANS BY OTHERS FOR ADDITIONAL INFORMATION AS APPLICABLE.

14. ALL WORK WITHIN THESE PLANS SHALL BE PERFORMED AND PROVIDED BY THE CONTRACTOR IN ACCORDANCE WITH THE CONSTRUCTION DETAILS PROVIDED IN THIS PLAN SET WHETHER OR NOT THE DETAIL NUMBER IS SPECIFICALLY REFERENCED.

15. ALL COVERS, CURB BOXES, GRATES, AND OTHER FINISH SURFACES SHALL BE RESET TO THE NEW FINISH GRADE.

16. THE FIRST 10 FEET FROM THE BUILDING FACE FOR STORM DRAIN, SEWER AND WATER PIPING SHALL FOLLOW THE PLUMBING CODE. THIS INCLUDES THE FIRST 10 FT OF STORM DRAIN AND SEWER PIPE TO BE CAST IRON MATERIAL. REFER TO PLUMBING PLANS BY OTHERS AS APPLICABLE.

17. WHERE UTILITIES CALLED OUT TO BE ABANDONED IN PLACE OR REMOVED AS NEEDED CONTRACTOR SHALL OWN REMOVING PIPE AND APPURTENANCES AS NEEDED WHERE THEY CONFIDENT WITH PROPERTIES WHERE

SEWER TESTING NOTES:

GRAVITY AND FORCEMAIN PIPING

1. PIPING PREPARATION

A LAMPING

1. LAWP GRANTY PIPING AFTER FLUSHING AND CLEANING.
2. PERFORM LAWPING OPERATION BY SHINNO LIGHT AT ONE END OF EACH PIPE SECTION BETWEEN WARHOLES; OBSERVE LIGHT AT OTHER END; REJECT PIPE NOT INSTALLED WITH UNFORM LINE AND GRADE, RELOVE AND REHISTALL REJECTED PIPE SECTIONS; RE-CLEAN AND LAWP UNTIL PIPE SECTION ACHIEVES UNFORM LINE AND GRADE.

A. GENERAL:

ALL SEMENS AND APPURITEMANT WORK, IN ORDER TO BE ELIGIBLE FOR ACCEPTANCE BY THE ENGINEER, SHALL BE SUBJECTED TO TESTS THAT WILL DETERMINE THE DEGREE OF WATER TIGHTNESS AND HORIZONTAL AND VERTICAL AUGMENT.

THOROUGHLY CLEAN AND/OR FLUSH ALL SEWER LINES TO BE TESTED, IN A MANNER AND TO THE EXTENT ACCEPTABLE TO THE ENGINEER, PRIOR TO INITIATING TEST PROCEDURES. PROCEDURES.

3. PERFORM LITESTS AND INSPECTIONS IN THE PRESENCE OF THE ENGINEER AND THE PLUMBING OR BUILDING INSPECTOR OR OTHER TOWN OFFICIAL IN ACCORDANCE WITH THE REGULARIZATION OF THE LOCAL AND STATE CODES.

4. PERFORM TESTING BY TEST PATTERNS DETERMINED BY OR ACCEPTABLE TO THE ENGINEER.

5. REVENUAL MORK!

DAL WORK:

OF PERFORM ALL WORK NECESSARY TO CORRECT DEFICIENCES DISCOVERED AS A RESULT OF TESTING AND/OR INSPECTIONS.

DEFICION ALL WORK NECESSARY TO CORRECT DEFICIENCES DISCOVERED AS A RESULT OF TESTING AND/OR INSPECTIONS.

COMPLETELY RETISST ALL PORTIONS OF THE ORIGINAL CONSTRUCTION ON WHICH REVEIRAL WORK HAS BEEN PERFORMED.

C. PERFORM ALL REZEDEAL WORK AND RETISTING IN A MARKER AND AT A TIME ACCEPTABLE TO THE ROSINEER AT NO ADDITIONAL COST TO THE OWNER.

B. TESTING GRAVITY SEWER PIPING:

LOW-PRESSURE AIR TEST:

0. TEST EACH SECTION OF GRAVITY SEWER PIPING.

b. INTRODUCE AIR PRESSURE SLOWLY TO APPROXIMATELY 4 PSIG.

1) DETERMINE GIOURD WATER LEVATION ABOVE SPRING LINE OF PIPE AND FOR EVERY FOOT OF GROUND WATER ABOVE SPRING LINE OF PIPE, INCREASE STARTING AN TEST PRESSURE DY 0.43 PSQ; DO NOT WORKERS PRESSURE ABOVE 00 PSQ;

c. ALLOW PRESSURE: TO STABLEZ FOR AT LEAST TIVE MINUTES. ADJUST PRESSURE. TO

3.5 PSG ON INCREASED TEST PRESSURE AS DETERMINED ABOVE WHEN GROUND WATER IS PRESENT, START TEST.

1. TEST.

1) DETERMINE TEST DURATION FOR SEWER SECTION WITH SINGLE PIPE SIZE FROM THE FOLLOWING TABLE, DO NOT MAKE ALLOWANCE FOR LATERALS.

NOMINAL PIPE SIZE (INCHES) = MINIMUM TEST TIME (MIN/ 100 FEET)

3" = 0.2; 4" = 0.3; 6" = 0.7; 8" = 1.2; 10"=1.5; 12"=1.8; 15"=2.1; 18"=2.4; 21"=3.0; 24"=3.6; 27"=4.2; 30"=4.8; 33"=5.4; 36"=6.0

RECORD DROP IN PRESSURE DURNG TEST PERIOD; WHEN AIR PRESSURE HAS DROPPED MORE THAN 1.0 PSG DURING TEST PERIOD, PIPING HAS FAILED; WHEN
1.0 PSIG AIR PRESSURE DROP HAS NOT OCCURRED DURING TEST PERIOD, DISCONTINUE TEST AND PIPING IS ACCEPTED.

THE PRINCE THE SOURCE UNLY HAS NOT OCCURRED DURING TEST PERIOD, DISCONTINUE TEST AND PIPING IS ACCEPTED.

3) WHEN PIPING FALS, DETERMINE SOURCE OF AIR LEMAKE, MAKE CORRECTIONS AND RETEST; TEST SECTION IN INCREMENTAL STAGES UNTIL LEAKS ARE ISOLATED; AFTER LEMAS ARE REPARED, RETEST ENTIRE SECTION BETWEEN MAINHOLES.

TEST PIPE LARGER THAN 36 INCHES DIAMETER WITH EXPLITATION TEST NOT EXCEEDING 100 GALLONS FOR EACH INCH OF PIPE DIAMETER FOR EACH MILE PER DAY FOR EACH INFAIRMON TEST.

INFLITATION TEST.

TION 1831:

1. USE ONLY WHEN GRAVITY PIPING IS SUBWERGED IN GROUND WATER MINIMUN OF 4 FEET ABOVE CROWN OF PIPE FOR ENTIRE LENGTH BEING TESTED.

1. MAXIMUM ALLOWABLE INFILTRATION: 100 GALLONS PER INCH OF PIPE DIAWETER FOR EACH MILE PER DAY FOR SECTION UNDER TEST, INCLUDE ALLOWANCES FOR LEXACGE FROM MAINTHOLES, PEPFORM TEST WITH MIRRIAMY POSTIVE HEAD OF 2 FEET.

C. TESTING PRESSURE SEWER PIPING:

OROSTATIC LEAKAGE TEST:

a. HYDROSTATICALLY TEST EACH PORTION OF PRESSURE PIPMS, INCLUDING VALVED SECTIONS, AT 1.5 TIMES WORKING PRESSURE OF PIPMS BASED ON ELEVATION OF TEST CAUGE.

b. FILL SECTION TO BE TESTED WITH MATER SLOWN, EXPEL AIR FROM PIPMS AT HIGH POINTS, INSTALL CORPORATION COCKS AT HIGH POINTS, CLOSE AR VENTS AND CORPORATION COCKS ATTER AR IS EXPELLED AND RASE PRESSURE TO SPECIFIED TEST PRESSURE.

c. GOSERIVE JOHNS, FITTINGS AND VALVES UNDER TEST, RELOVE AND RELVEN GRACKED PPE, JOHNS, FITTINGS, AND VALVES SHOWNEN VISIBLE LEAKAGE, RETEST, ACCORDITIONAL TO SHOULD TO SET OF THE STATE AND THE SECOND AT SAME TEST PRESSURE OR DOTTONIAL TO PRESSURE AND THE STATE AND THE STAT

a. COMPUTE MAXIMUM ALLOWABLE LEAKAGE BY THE FOLLOWING FORMULA:

L = (S L D L ·P) + C L = ALLOWABLE (EAKAGE, IN GALLONS PER HOUR S = LENGTH OF PPE, TESTED, IN PERIOD D = NOWINAL OMACTER OF PPE, IN INCHES P = AVERAGE TEST PRESSURE DURING LEAKAGE TEST, IN PSIG C = 133,200

WHEN PIPE UNDER TEST CONTAINS SECTIONS OF VARIOUS DIAMETERS, CALCULATE ALLOWABLE LEAKAGE FROM SUM OF COMPUTED LEAKAGE FOR EACH SIZE,

I. WHEN TEST OF PIPE INDICATES LEAKAGE GREATER THAN ALLOWED, LOCATE SOURCE OF LEAKAGE, MAKE CORRECTIONS AND RETEST UNTIL LEAKAGE IS WITHIN ALLOWABLE LIMITS. CORRECT VISBLE LEAKS REGARDLESS OF QUANTITY OF LEAKAGE.

PERFORM VERTICAL RING DEFLECTION TESTING ON PVC AND ABS SEWER PIPHIG, AFTER BACKFILLING HAS BEEN IN PLACE FOR AT LEAST 30 DAYS BUT NOT LONGER THAN 12

MONTHS.

ALLOWABLE MAXIMUM DEFLECTION FOR INSTALLED PLASTIC SEMER PIPE LIMITED TO 5 PERCENT OF ORIGINAL VERTICAL INTERNAL DIAMETER.

PERFORM DEFLECTION TESTING USING PROPERLY SIZED RIGID BALL OR 'CO, NO-GO' MANDREL.

FURNISH RIGIO BALL OR MARKEL MITH DIAMETER NOT LESS THAN 99 PERCENT OF BASE OR AVERAGE INSDE DIAMETER OF PIPE AS DETERMINED BY ASTM STANDARD TO WHICH PIPE IS MANUFACTURED, MEASURE PIPE IN COMPUNION. WITH ASTM D2122.

PERFORM TEST MITHOUT MECHANICA, PULLING DEVICES.

LOCATE, EXCAVATE, REPLACE AND RETEST PIPE EXCEEDING ALLOWABLE DEFLECTION.

E. TELEVISION INSPECTION TESTS (GRAVITY SEWERS):

NO STANDING WATER SHALL BE ALLOWED. THE PRESENCE OF STANDING WATER MAY BE CAUSE FOR REJECTION OF THAT PIPE.

ANY STANDING WATER, DETECTABLE LEAKS, IMPROPER JOINTS OR ANY OTHER UNACCEPTABLE FEATURE DETECTED BY THE TELEVISION INSPECTION WILL BE CORRECTED BY RE-EXCAVATION AND RESETTING PIPE AT NO ADDITIONAL COST TO THE OWNER.

BAXTER

BAXTER NYE ENGINEERING & SURVEYING

Registered Professional Engineers and Land Surveyors

78 North Street - 3rd Floor

Phone - (508) 771-7502 Fax - (508) 771-7622 www.baxter-nye.com

STAMP	STAMP

CONSULTANT

CONSULTANT

PREPARED FOR:

SOUTHWORTH MASHPEE PROPERTIES, LLC 130 Willowbend Drive Mashpee MA 02549

PROJECT TITLE

Willowbend Country Club Clubhouse Villas

ı				
I				
ı				
ı				
ı				
I				
l				
l				
l				
l				
l				
l			DATE	DESCRIPTION
1	0 1	100	T TITE	E


Utility Plan and Notes

C5.0


DATE	: APRIL 14, 2	020
20	0	20
	COALE	IN EEET

SCALE: 1"=20'


FOR PERMIT ONLY - NOT FOR CONSTRUCTION PRAWN BY: SOM



OCENTRES - DOS AND VICTURE HOOM-VANISHED HORD CLUB HAR



GAZHAZEL+DODGTVLPLOTVZLUB ROOM-VIIMVZEH-UB9 GLUB KWB CE 0 CELT DT.omg. 4/14/200



Jeffrey Yates Architecture 60 Thorsou Street, Suite 112 Concord, MA 01742 978-952-2525 www.jputesarch.com


DATE PERMIT SET 8-14-13 CONSTRUCTION 9-12-13 REV. CONST. 1-20-1 REV. CONST. 9-18-1 PERMIT SET 7-24-17

FIRST FLOOR PLAN VILLA 3 STORY

64 Simonds Road The Village at Willowbend

SCALE: SHOWN

DRAWN BY





Jeffrey Yates Architecture 60 Thoreou Street, Suits 112 Concord, MA 01742 978-952-2525 www.jyatesarch.com

Coyright Jeffrey Yobse Architects 2009

ISSUED DATE	PERMIT SET 8-14 CONSTRUCTION 9-12 REV. CONST. 1-20 REV. CONST. 9-18		
CONSTRUCTION 9-12- REV. CONST. 1-20 REV. CONST. 9-18	CONSTRUCTION 9-12- REV. CONST. 1-20 REV. CONST. 9-18	ISSUED	DATE
REV. CONST. 1-20 REV. CONST. 9-18	REV. CONST. 1-20 REV. CONST. 9-18	PERMIT SET	8-14
REV. CONST. 9-18	REV. CONST. 9-18	CONSTRUCTION	912
		REV. CONST.	1-20
PERMIT SET 7-24	PERMIT SET 7-24	REY. CONST.	9-18
		PERMIT SET	724
		T COMM GET	1 -
		.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
			+
			+-
			1
			+-
	,		<u> </u>


SECOND FLOOR PLAN
VILLA
3 STORY

64 Simonds Road The Village at Willowbend

Mashpee, MA

SCALE: SHOWN DRAWN BY







Jeffrey Yates Architecture 50 Thoreou Street, Suite 112 Concord, MA 01742 978-952-2525 www.butesarch.com

Coyright Jeffrey Yolas Architecta 2009


ISSUED	DATE
PERMIT SET	8-14-
CONSTRUCTION	9-12-
REV. CONST.	1-20-
REV. CONST.	9-18-
	<u> </u>
PERMIT SET	7-24-
	-
	+
	··
	1
	
	


THIRD FLOOR PLAN
VILLA
3 STORY


64 Simonds Road
The Village
at
Willowbend
Mashpee, MA


SCALE: SHOWN
DRAWN BY











PROPOSED WINDOW SCHEDULE - TO BE VERIFIED

	TYPE PE	LLA DESIGNATION	ROUGH OPENING	REMARKS	QTY
Α	DH	2959	29 3/4 " X 59 3/4"	TEMP. WHERE REQ.	70
Α/T	TRANS	2959/2917	29 3/4" X 76 3/4"		10
С	CSMNT	2341	23 3/4" X 41 3/4"	6 LEFT/6 RIGHT	12
D	SL, GL, DR	0896	108 ¾" X 96		12
Е	GL.DOOR/TRAN	7286/71.2514	72" X 100 ½"		4
F'	FIXED GL. DR/TRAN	3686/3614	36 ¾" X 100 Ĵ"		8
G	GL. DR/TRAN	7286/71.2525	72" X 111 🖟		2
Н	FIXED GL. DR/TRAN	\$686/3625	36 ≩" X 111 Ž"		4
1	FIXED	2935	29 ¾" X 35 ¾"		2
J	AWNING	2929	29 ¾" X 29 ¾"		1

CONTRACTOR TO VERIFY ALL SIZES AND QUANTITIES AND GRILL OPTIONS BEFORE PLACING ORDER.







Coyright Jeffrey Yokes Architects 2009

ISSUED	DATE
PERMIT SET	8-14-1
CONSTRUCTION	9-12-1
REV. CONST.	1-20-1
REV. CONST.	9-18-1
	1
PERMIT SET	7-24-1
	<u> </u>

ELEVATIONS, DETAILS VILLA

3 STORY

64 Simonds Road The Village at Willowbend

Mashpee, MA

SCALE: SHOWN







Jeffrey Yates Architecture 80 Thoreau Street, Suite 112 Concord, MA 01742 978-952-2525 www.jyatesarch.com Coptight Juffrey Yotes Architects 2009

> VILLA 3 STORY

64 Simonds Road
The Village
at
Willowbend
Moshpee, MA

SCALE: SHOWN DRAWN BY

<u>A</u>-6

BAXTER NYE

ENGINEERING & SURVEYING

STORMWATER MANAGEMENT REPORT for

CLUB ROOM VILLAS AT WILLOWBEND

WILLOWBEND DRIVE
WILLOWBEND COUNTRY CLUB
MASHPEE, MASSACHUSETTS

Prepared for:

SOUTHWORTH MASHPEE PROPERTIES, LLC

130 WILLOWBEND DRIVE
MASHPEE, MASSACHUSETTS

APRIL 14, 2020

BAXTER NYE ENGINEERING & SURVEYING

Registered Professional Engineers, Land Surveyors & Scientists

78 North Street, 3rd Floor ■ Hyannis, MA 02601
Tel: 508-771-7502 ■ Fax: 508-771-7622 ■ <u>www.baxter-nye.com</u>

BAXTER NYE ENGINEERING & SURVEYING

Registered Professional Engineers and Land Surveyors

78 North Street, 3rd Floor, Hyannis, MA 02601 T

Tel: (508) 771-7502 Fax: (508) 771-7622

PROJECT STATEMENT

PROJECT: Proposed Condominiums

LOCATION: Willowbend Drive Willowbend Country Club, Mashpee, MA

BN JOB NUMBER: 2014-009

CLIENT: Southworth Mashpee Properties, LLC

SUBJECT: Stormwater Management & Drainage Calculations

OBJECTIVES:

- 1) Meet the objectives of the Town of Mashpee Zoning Ordinance & MA DEP SWM Policy
 - (a) Evaluate the pre-development conditions and calculate the peak rate of runoff.
 - (b) Evaluate the post-development conditions and provide stormwater management and treatment to prevent any increase in the 2 and 10-year storms, from the pre-development conditions peak discharge at the site study point.
 - (c) Safely pass the 100-year storm event without causing any downstream detrimental impact.
 - (d) Provide for Water Quality Treatment for the first flush 0.5" of rainfall in accordance with MDEP SWM Policy
 - (e) Provide for Groundwater Recharge in accordance with MDEP SWM Policy.

CALCULATION METHODS & DESIGN STORMS:

- 1) Soil information was taken from the SCS Soil Survey of Barnstable County.
- 2) Sub-catchment areas, flow paths, and design points were delineated using standard engineering practice.
- 3) The existing and proposed conditions were modeled using HydroCAD, which incorporates the methodologies of SCS TR-55 and TR-20.
- 4) The proposed stormwater management system was designed to control the 2, 10, and 25-year storm event using the SCS TR-20 Method. The 100-year storm event will pass safely through the system with no detrimental impact to downstream areas.
- 5) Private closed storm drain systems shall be sized for the 10-year storm event. Inlets and curb openings shall be analyzed for the 10-year storm event. All storm drain calculations will use the rational method.
- 6) Ditch and channel flow shall be analyzed for the 10-year storm event. Ditch and channel flow around buildings shall be analyzed for the 100-year event.

PROJECT NARRATIVE

Club Room Villas at Willowbend is a proposed project located within Willowbend Country Club and fronts on Quiniquisett Road. The project area is approximately 1.4 acres. The lot is zoned residential (R3) and the allowed use for the lot is residential. The project area is undeveloped. and is currently vacant. The project consists of a new residential townhome building. The proposed buildings consist of 6 units and vary between approximately 2,000 to 2,400 square feet per unit.

The proposed stormwater management systems (SMS) will be installed to control stormwater runoff for water quality and quantity in accordance with MDEP SWM Policy. Under the proposed conditions, both stormwater quantity and quality are controlled. The post-development peak storm discharges are reduced to pre-development levels or below for the 2, 10 and 25-year storms. The 100-year event is controlled, and all runoff is safely conveyed. The post-development water quality is treated through the SMS which provides an 80% or better total suspended solid (TSS) removal rate. The water recharge will be affected positively, as it will receive the same volume of runoff, but at attenuated peaks, thereby, reducing velocities and erosion.

SUMMARY

Based on the analysis performed for the 2, 10, 25 and 100-year storm events, the infiltration basin is adequately sized to mitigate potential increases in the peak rate of runoff and volume from the site. The "Discarded" flows shown within the HydroCAD analysis represent flows and volumes infiltrated directly into the ground through the SWM structures and are not discharged or released over land.

Table 1 is a summary of expected release rates based on total contributing drainage areas (both on-site and off-site areas). This table shows the expected post development runoff rates and volumes are decreased from the pre-development levels for the 2, 10, 25 and 100-year storms. The SWM systems treat, store and infiltrate (recharges) the post-development runoff volume for the 2, 10, 25 and 100-year storms. The control of the post-development volume to well below pre-development levels mitigates any downstream/offsite flooding impacts and provides for significant groundwater recharge. The benefit to the groundwater recharge is greatly enhanced, as shown by the reduction of volume runoff from the site for the 2, 10, 25 and 100-year events.

TABLE 1: PEAK DISCHARGE AND VOLUME RELEASE

STORM (YEAR)	DRAINAGE AREA	PRE-DEVELOPMENT		POST DEVELOPMENT	
		PEAK DISCHARGE (cfs)	VOLUME (ac-ft)	PEAK DISCHARGE (cfs)	VOLUME (ac-ft)
2	STUDY POINT #1	0.24	0.038	0.22	0.022
10	STUDY POINT #1	1.22	0.110	0.59	0.059
25	STUDY POINT #1	2.14	0.171	1.07	0.113
100	STUDY POINT #1	3.79	0.280	2.61	0.216

RECHARGE TO GROUNDWATER VOLUME

(MADEP Standard 3)

All site soils within area of proposed impervious cover are HSG A. Therefore, the recharge rate is:

- = 0.4" x total impervious area
- = 0.4" x 0.27 acres (roads and driveways) + 0.11 acres (roofs) = 0.38 acres
- = 0.152 ac-in.
- = 0.0127 ac.ft.
- = 552 cf

The Infiltration SWM Facility is used for recharge and quantity control for post-development site runoff.

1) SWM Facility: Infiltration Storage Volume Provided up to Elevation 18.00:

= 1,970 cf

Therefore, total Volume of Recharge which is provided:

= 1,970 cf > 552 cf / Design Reqmts met

The Volume of Recharge well exceeds the required amount of recharge.

WATER QUALITY VOLUME CALCULATIONS

(MADEP Standard 4-6)

The site is not within a Zone II Recharge Area, which is defined as a Critical Area. Therefore, the Water Quality Treatment must address the first half inch (0.5") of runoff over the total impervious area. The proposed increased on-site impervious area equals 0.38 acres. The proposed building roof area is 0.11 acres, which is conveyed directly to the swm basins and does not required water quality treatment. The total impervious area to receive water quality treatment is 0.27 acres.

WQV = 0.5"x (acres of impervious area)

- = 0.5" x (0.27 acres)
- = 0.135 acre-inches
- = 0.135/12 in/ft
- = 0.01125 acre-feet
- = 0.01125 acre-feet x 43,560 sf/ac = 490 +/- cubic feet

The total WQV to be treated through BMP's is 490 cf.

The total water quality treatment volume provided = 493 cubic feet at elevation 17.0

FIGURE 1

Pre-Development Drainage Plan

FIGURE 2

Post Development Drainage Plan

TSS REMOVAL CALCULATION WORKSHEET

PROPOSED

location CLUB ROOMS
Job # 2014-009

TSS REMOVAL CALCULATION WORKSHEET


SWM FACILITY

A BMP	B TSS Removal Rate	C Starting TSS Load *	D Amount Removed (BxC)	E Remaining Load (C-D)
Sediment Forebay	25%	1.00	0.25	0.75
Infiltration Basin	80%	0.75	0.60	0.15
		Total TSS Removed =	0.85	

^{*}Equals remaining load from previous BMP (E)

APPENDIX A

PRE-DEVELOPMENT WATERSHED RUNOFF & ROUTING



EXISTING PARKING, CART PATH AND ABUTTING EXISTING POND

GRASS AND CART PATH ABUTTING POND









HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Prepared by BAXTER-NYE ENGINEERING
HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Printed 4/14/2020 Page 2

Area Listing (all nodes)

Area	CN	Description
 (acres)		(subcatchment-numbers)
0.930	39	>75% Grass cover, Good, HSG A (DA-1, DA-2)
0.380	98	Paved parking, HSG A (DA-1, DA-2)
0.140	30	Woods, Good, HSG A (DA-1)
1.450	54	TOTAL AREA

Prepared by BAXTER-NYE ENGINEERING
HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Printed 4/14/2020

Page 3

Ground Covers (all nodes)

 HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
 0.930	0.000	0.000	0.000	0.000	0.930	>75% Grass cover, Good	DA-1,
							DA-2
0.380	0.000	0.000	0.000	0.000	0.380	Paved parking	DA-1,
							DA-2
0.140	0.000	0.000	0.000	0.000	0.140	Woods, Good	DA-1
1.450	0.000	0.000	0.000	0.000	1.450	TOTAL AREA	

Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 4


Summary for Subcatchment DA-1: EXISTING PARKING, CART PATH AND ABUTTING EXISTING PON

Runoff = 0.24 cfs @ 12.13 hrs, Volume= 0.034 af, Depth= 0.38"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 2-YR MASHPEE Rainfall=3.50"

_	Area	(ac)	CN	Desc	Description						
	0.	610	10 39 >75% Grass cover, Good, HSG A								
	0.	140	30	Woo	Woods, Good, HSG A						
_	0.	330 98 Paved parking, HSG A									
	1.	1.080 56 Weighted Average									
	0.	750		69.4	4% Pervio	us Area					
	0.330 30			30.5	30.56% Impervious Area						
	Tc	Leng		Slope	Velocity	Capacity	Description				
_	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)					
	5.0						Direct Entry				

Subcatchment DA-1: EXISTING PARKING, CART PATH AND ABUTTING EXISTING POND



Printed 4/14/2020

Page 5


Summary for Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND

Runoff = 0.01 cfs @ 12.49 hrs, Volume= 0.004 af, Depth= 0.12"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 2-YR MASHPEE Rainfall=3.50"

A	rea (ad	c) CN	Des	cription		
	0.32	0 39	>75°	% Grass c	over, Good	I, HSG A
	0.05	0 98	Pave	ed parking	, HSG A	
	0.37	0 47	. Wei	ghted Aver	age	
	0.32	0	86.4	9% Pervio	us Area	
	0.050			1% Imperv	ious Area	
(m		ength (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	5.0					Direct Entry, L1

Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND



Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 6

Summary for Reach SP#1: STUDY POINT #1


Inflow Area = 1.450 ac, 26.21% Impervious, Inflow Depth = 0.31" for 2-YR MASHPEE event

Inflow = 0.24 cfs @ 12.13 hrs, Volume= 0.038 af

Outflow = 0.24 cfs @ 12.13 hrs, Volume= 0.038 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3

Reach SP#1: STUDY POINT #1



Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 7


Summary for Subcatchment DA-1: EXISTING PARKING, CART PATH AND ABUTTING EXISTING PON

Runoff = 1.12 cfs @ 12.09 hrs, Volume= 0.094 af, Depth= 1.04"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 10-YR MASHPEE ATLAS Rainfall=5.00"

Area	(ac)	CN	Desc	Description					
0.	610	39	>75%	ն Grass co	over, Good	I, HSG A			
0.	140	30	Woo	ds, Good,	HSG A				
0.	330	98	Pave	d parking	, HSG A				
1.080 56 Weighted Average									
0.	0.750 69.44% Pervious Are								
0.	0.330			3% Imper	ious Area				
_			21		0 :	B 1.0			
Tc	Lengi		Slope	Velocity	Capacity	Description			
(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)				
5.0						Direct Entry,			

Subcatchment DA-1: EXISTING PARKING, CART PATH AND ABUTTING EXISTING POND



Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 8


Summary for Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND

Runoff = 0.11 cfs @ 12.13 hrs, Volume= 0.017 af, Depth= 0.54"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 10-YR MASHPEE ATLAS Rainfall=5.00"

Area	(ac)	CN	Desc	Description					
0.	320	39	>75%	√ Grass co	over, Good	, HSG A			
0.	0.050 98 Paved parking, HSG A								
0.	370	47	Weig	hted Aver	age				
0.	320		86.4	86.49% Pervious Area					
0.	050		13.5	1% Imperv	ious Area				
Tc	Leng		Slope	Velocity	Capacity	Description			
(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)				
5.0						Direct Entry, L1			

Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND



Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 9

Summary for Reach SP#1: STUDY POINT #1


Inflow Area = 1.450 ac, 26.21% Impervious, Inflow Depth = 0.91" for 10-YR MASHPEE ATLAS event

Inflow = 1.22 cfs @ 12.10 hrs, Volume= 0.110 af

Outflow = 1.22 cfs @ 12.10 hrs, Volume= 0.110 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3

Reach SP#1: STUDY POINT #1



Page 10


Summary for Subcatchment DA-1: EXISTING PARKING, CART PATH AND ABUTTING EXISTING PON

Runoff = 1.86 cfs @ 12.09 hrs, Volume= 0.143 af, Depth= 1.58"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 25-YR MASHPEE ATLAS Rainfall=5.98"

_	Area	(ac)	CN	Desc	Description						
	0.	610	S10 39 >75% Grass cover, Good, HSG A								
	0.	140	30) Woods, Good, HSG A							
_	0.	330 98 Paved parking, HSG A									
	1.	1.080 56 Weighted Average									
	0.	750		69.4	4% Pervio	us Area					
	0.330 30				30.56% Impervious Area						
	_										
	Tc	Leng		Slope	Velocity	Capacity	Description				
	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)					
	5.0						Direct Entry				

Subcatchment DA-1: EXISTING PARKING, CART PATH AND ABUTTING EXISTING POND



Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 11


Summary for Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND

Runoff = 0.29 cfs @ 12.10 hrs, Volume= 0.029 af, Depth= 0.92"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 25-YR MASHPEE ATLAS Rainfall=5.98"

	Area	(ac)	CN	Desc	Description					
	0.	320	39	>75%	% Grass co	over, Good	, HSG A			
	0.	0.050 98 Paved parking, HSG A								
	0.370 47 Weighted Avera					age				
	0.	320		86.4	9% Pervio	us Area				
	0.050			13.5	1% Imperv	∕ious Area				
	То	Long	th	Clana	Volocity	Consoity	Description			
	Tc (min)	Leng		Slope	Velocity	Capacity	Description			
_	(min)	(fee	ι)	(ft/ft)	(ft/sec)	(cfs)				
	5.0						Direct Entry, L1			

Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND



Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 12

Summary for Reach SP#1: STUDY POINT #1


Inflow Area = 1.450 ac, 26.21% Impervious, Inflow Depth = 1.42" for 25-YR MASHPEE ATLAS event

Inflow = 2.14 cfs @ 12.09 hrs, Volume= 0.171 af

Outflow = 2.14 cfs @ 12.09 hrs, Volume= 0.171 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3

Reach SP#1: STUDY POINT #1



Page 13


Summary for Subcatchment DA-1: EXISTING PARKING, CART PATH AND ABUTTING EXISTING PON

Runoff = 3.17 cfs @ 12.08 hrs, Volume= 0.229 af, Depth= 2.54"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 100-YR MASHPEE ALTAS Rainfall=7.49"

_	Area	(ac)	CN	Desc	Description						
	0.	610	S10 39 >75% Grass cover, Good, HSG A								
	0.	140	30) Woods, Good, HSG A							
_	0.	330 98 Paved parking, HSG A									
	1.	1.080 56 Weighted Average									
	0.	750		69.4	4% Pervio	us Area					
	0.330 30				30.56% Impervious Area						
	_										
	Tc	Leng		Slope	Velocity	Capacity	Description				
	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)					
	5.0						Direct Entry				

Subcatchment DA-1: EXISTING PARKING, CART PATH AND ABUTTING EXISTING POND



Page 14


Summary for Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND

Runoff = 0.63 cfs @ 12.09 hrs, Volume= 0.051 af, Depth= 1.66"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 100-YR MASHPEE ALTAS Rainfall=7.49"

	Area	(ac)	CN	Desc	Description					
	0.	320	39	>75%	√ Grass co	over, Good	, HSG A			
	0.	0.050 98 Paved parking, HSG A								
	0.	370	47	Weig	hted Aver	age				
	0.	320		86.4	86.49% Pervious Area					
	0.050			13.5	1% Imperv	ious Area				
	_		41.	01	V . I	0	Description			
	Tc	Leng		Slope	Velocity	Capacity	Description			
((min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)				
	5.0						Direct Entry, L1			

Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND



Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 15

Summary for Reach SP#1: STUDY POINT #1


Inflow Area = 1.450 ac, 26.21% Impervious, Inflow Depth = 2.32" for 100-YR MASHPEE ALTAS event

Inflow = 3.79 cfs @ 12.08 hrs, Volume= 0.280 af

Outflow = 3.79 cfs @ 12.08 hrs, Volume= 0.280 af, Atten= 0%, Lag= 0.0 min


Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3

Reach SP#1: STUDY POINT #1



APPENDIX B

POST- DEVELOPMENT WATERSHED RUNOFF & ROUTING



2014-009 CLUB RMS PROPOSED WITH FOREBAY CALCS

Prepared by BAXTER-NYE ENGINEERING
HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Printed 4/14/2020 Page 2

Area Listing (selected nodes)

Are	ea CN	Description
(acre	s)	(subcatchment-numbers)
0.8	35 39	>75% Grass cover, Good, HSG A (DA-1A, DA-1B, DA-1C, DA-2)
0.30	00 98	Paved parking, HSG A (DA-1B, DA-2)
0.13	35 98	Paved roads w/curbs & sewers, HSG A (DA-1A, DA-1C)
0.1	10 98	Roofs, HSG A (R1)
0.04	42 30	Woods, Good, HSG A (DA-1B, DA-1C)
1.4	22 61	TOTAL AREA

2014-009 CLUB RMS PROPOSED WITH FOREBAY CALCS

Prepared by BAXTER-NYE ENGINEERING

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Printed 4/14/2020 Page 3

Ground Covers (selected nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.835	0.000	0.000	0.000	0.000	0.835	>75% Grass cover, Good	DA
							-1A
							, DA
							-1B
							, DA
							-1C
							,
							DA
							-2
0.300	0.000	0.000	0.000	0.000	0.300	Paved parking	DA
							-1B
							, DA
							-2
0.135	0.000	0.000	0.000	0.000	0.135	Paved roads w/curbs & sewers	_ DA
							-1A
							,
							DA
0.440	0.000	0.000	0.000	0.000	0.440	D (-1C
0.110 0.042	0.000 0.000	0.000 0.000	0.000 0.000	0.000 0.000	0.110 0.042	Roofs Woods, Good	R1 DA
0.042	0.000	0.000	0.000	0.000	0.042	woods, Good	-1B
							, DA
							-1C
1.422	0.000	0.000	0.000	0.000	1.422	TOTAL AREA	

Page 4


Summary for Subcatchment DA-1A: GRASS ABUTTING EXISTING POND

Runoff = 0.00 cfs @ 14.73 hrs, Volume= 0.002 af, Depth= 0.08"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 2-YR MASHPEE Rainfall=3.50"

	Area	(ac)	CN	Desc	Description						
	0.	194	39	>75%	6 Grass co	over, Good	d, HSG A				
	0.	024	98	Pave	ed roads w	/curbs & se	ewers, HSG A				
	0.	218	45	Weig	hted Aver	age					
	0.	194		88.99	9% Pervio	us Area					
	0.	024		11.0	1% Imperv	ious Area					
	-		41. 4	.	V/. I	0	D				
	Tc Length Slope Velocity Capacity Description										
_	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)					
	5.0						Direct Entry,				

Subcatchment DA-1A: GRASS ABUTTING EXISTING POND



Page 5


Summary for Subcatchment DA-1B: PARKING LOT

Runoff = 0.50 cfs @ 12.09 hrs, Volume= 0.038 af, Depth= 0.95"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 2-YR MASHPEE Rainfall=3.50"

	Area	(ac)	CN	Desc	Description								
_	0.	197	39	>75%	>75% Grass cover, Good, HSG A								
	0.	0.028 30 Woods, Good, HSG A											
_	0.	249	98	Pave	ed parking	HSG A							
_	0.	474	69	Weig	hted Aver	age							
	0.	225		47.4	7% Pervio	us Area							
0.249 52.53% lm					3% Imperv	ious Area							
	Tc Length Slope Velocity Capacity Description												
_	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)							
	5.0						Direct Entry						

Subcatchment DA-1B: PARKING LOT



Page 6


Summary for Subcatchment DA-1C: CLUB HOUSE AND CART PATH

Runoff = 0.22 cfs @ 12.09 hrs, Volume= 0.017 af, Depth= 0.95"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 2-YR MASHPEE Rainfall=3.50"

_	Area	(ac)	CN	Desc	Description							
	0.	088	39	>759	% Grass co	over, Good	d, HSG A					
	0.	014	30	Woo	ds, Good,	HSG A						
_	0.	111	98	Pave	ed roads w	/curbs & se	sewers, HSG A					
_	0.	213	69	Weig	hted Aver	age						
	0.	102		47.8	9% Pervio	us Area						
	0.111 52.11% Impervious Area											
	Tc Length Slope Velocity Capacity Description											
_	(min)	nin) (feet) (ft/ft) (ft/sec) (cfs)										
	5.0						Direct Entry					

Subcatchment DA-1C: CLUB HOUSE AND CART PATH



Page 7


Summary for Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND

Runoff = 0.01 cfs @ 13.77 hrs, Volume= 0.003 af, Depth= 0.10"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 2-YR MASHPEE Rainfall=3.50"

A	rea (a	c) CN	l Des	Description								
	0.35	56 39) >75°	% Grass co	over, Good	I, HSG A						
	0.05	51 98	B Pave	ed parking	, HSG A							
	0.40	07 46	6 Wei	ghted Aver	age							
	0.35	56	87.4	7% Pervio	us Area							
	0.051 12.53% Impervious A				ious Area							
(m	Tc Length (min) (feet)		Slope Velocity Capacity (ft/ft) (ft/sec) (cfs)		. ,	Description						
	5.0					Direct Entry, L1						

Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND



Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 8


Summary for Subcatchment R1: ROOF

Runoff = 0.39 cfs @ 12.07 hrs, Volume= 0.030 af, Depth= 3.27"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 2-YR MASHPEE Rainfall=3.50"

	Area	(ac)	CN	Desc	cription			
	0.110 98 Roofs, HSG A							
_	0.110 100.00% Impervious Area							
	Tc	Lengt	h S	Slope	Velocity	Capacity	Description	
	(min)	(feet	t)	(ft/ft)	(ft/sec)	(cfs)	·	
	5.0						Direct Entry, Minimum	

Subcatchment R1: ROOF



2014-009 CLUB RMS PROPOSED WITH FORE Type III 24-hr 2-YR MASHPEE Rainfall=3.50"

Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 9

Summary for Reach SP#1: STUDY POINT #1


Inflow Area = 1.422 ac, 38.33% Impervious, Inflow Depth = 0.19" for 2-YR MASHPEE event

Inflow = 0.22 cfs @ 12.09 hrs, Volume= 0.022 af

Outflow = 0.22 cfs @ 12.09 hrs, Volume= 0.022 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3

Reach SP#1: STUDY POINT #1



Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

<u>Page 10</u>

Summary for Pond P-1: POND/BIOSWALE

Inflow Area = 0.584 ac, 61.47% Impervious, Inflow Depth = 0.98" for 2-YR MASHPEE event

Inflow = 0.75 cfs @ 12.13 hrs, Volume= 0.048 af

Outflow = 0.07 cfs (a) 13.07 hrs, Volume= 0.048 af, Atten= 90%, Lag= 56.3 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3

Peak Elev= 17.25' @ 13.07 hrs Surf.Area= 1,304 sf Storage= 798 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 98.6 min (863.5 - 764.9)

Volume	Inve	rt Avail	.Storage	ge Storage Description				
#1	16.50)'	4,156 cf	Custom Stage D	ata (Irregular) List	ed below (Recalc)		
Elevation		Surf.Area	Perim.	Inc.Store	Cum.Store	Wet.Area		
(fee	et)	(sq-ft)	(feet)	(cubic-feet)	(cubic-feet)	<u>(sq-ft)</u>		
16.5	50	831	207.0	0	0	831		
17.0	00	1,150	217.0	493	493	1,185		
18.0	00	1,829	236.0	1,476	1,970	1,906		
19.0	00	2,564	255.0	2,186	4,156	2,688		
Device	Routing	ln۱	ert Outle	et Devices			_	
#1	Discarded	d 16.	.50' 2.41	0 in/hr Exfiltration	n over Surface ar	ea		
#2	Primary	18.	.00' 5.0'	long x 9.0' bread	th Broad-Crested	l Rectangular Weir		
			Head	d (feet) 0.20 0.40	0.60 0.80 1.00	1.20 1.40 1.60 1.80 2.00		
			2.50	3.00 3.50 4.00	4.50 5.00 5.50			
			Coef	f. (English) 2.46 2	2.55 2.70 2.69 2.	68 2.68 2.67 2.64 2.64		
			2.64	2.65 2.64 2.65	2.65 2.66 2.67 2	.69		

Discarded OutFlow Max=0.07 cfs @ 13.07 hrs HW=17.25' (Free Discharge) **1=Exfiltration** (Exfiltration Controls 0.07 cfs)


Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=16.50' TW=0.00' (Dynamic Tailwater) 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Printed 4/14/2020

Page 11

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Pond P-1: POND/BIOSWALE



Page 12

Summary for Pond P-2: FOREBAY

Inflow Area = 0.474 ac, 52.53% Impervious, Inflow Depth = 0.95" for 2-YR MASHPEE event

Inflow 0.50 cfs @ 12.09 hrs, Volume= 0.038 af

0.47 cfs @ 12.13 hrs, Volume= Outflow 0.038 af, Atten= 5%, Lag= 2.8 min

0.02 cfs @ 12.13 hrs, Volume= Discarded = 0.020 af Primary = 0.45 cfs @ 12.13 hrs, Volume= 0.018 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3

Peak Elev= 17.61' @ 12.13 hrs Surf.Area= 334 sf Storage= 254 cf

Plug-Flow detention time= 95.9 min calculated for 0.038 af (100% of inflow)

Center-of-Mass det. time= 96.0 min (967.7 - 871.7)

Volume	Inver	t Avail.S	torage	Storage Descripti	on	
#1	16.50)'	640 cf	Custom Stage D	ata (Irregular)List	ed below (Recalc)
Elevatio		Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
16.5	50	136	47.0	0	0	136
17.0	00	215	58.0	87	87	232
17.5	50	310	68.0	131	218	337
18.0	00	420	79.0	182	399	471
18.5	50	547	89.0	241	640	611
Device	Routing	Inve	rt Outle	et Devices		
#1	Discarded	l 16.50)' 2.41	0 in/hr Exfiltration	n over Surface ar	ea
#2	Primary	17.50	D' 5.0'	long x 6.0' bread	th Broad-Crested	d Rectangular Weir
			Head	d (feet) 0.20 0.40	0.60 0.80 1.00	1.20 1.40 1.60 1.80 2.00
			2.50	3.00 3.50 4.00	4.50 5.00 5.50	
			Coef	f. (English) 2.37 2	2.51 2.70 2.68 2.	68 2.67 2.65 2.65 2.65
			2.65	2.66 2.66 2.67	2.69 2.72 2.76 2	.83

Discarded OutFlow Max=0.02 cfs @ 12.13 hrs HW=17.61' (Free Discharge) 1=Exfiltration (Exfiltration Controls 0.02 cfs)


Primary OutFlow Max=0.41 cfs @ 12.13 hrs HW=17.61' TW=16.83' (Dynamic Tailwater) 2=Broad-Crested Rectangular Weir (Weir Controls 0.41 cfs @ 0.77 fps)

Printed 4/14/2020

Page 13

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Pond P-2: FOREBAY



Page 14


Summary for Subcatchment DA-1A: GRASS ABUTTING EXISTING POND

Runoff = 0.04 cfs @ 12.29 hrs, Volume= 0.008 af, Depth= 0.44"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 10-YR MASHPEE ATLAS Rainfall=5.00"

	Area	(ac)	CN	Desc	ription		
	0.	194	39	>75%	6 Grass co	over, Good	d, HSG A
	0.	024	98	Pave	ed roads w	/curbs & se	ewers, HSG A
	0.	218	45	Weig	hted Aver	age	
	0.	194		88.99	9% Pervio	us Area	
	0.024 11.01% Impervious Area						
	_					• "	
	Tc	Leng		Slope	Velocity	Capacity	Description
_	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)	
	5.0						Direct Entry,

Subcatchment DA-1A: GRASS ABUTTING EXISTING POND



Page 15


Summary for Subcatchment DA-1B: PARKING LOT

Runoff = 1.09 cfs @ 12.08 hrs, Volume= 0.077 af, Depth= 1.96"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 10-YR MASHPEE ATLAS Rainfall=5.00"

Area	(ac)	CN	Desc	cription		
0.	.197	39	>75%	√ Grass co	over, Good	d, HSG A
0.	.028	30	Woo	ds, Good,	HSG A	
0.	.249	98	Pave	ed parking	HSG A	
0.	.474	69	Weig	hted Aver	age	
0.	.225		47.4	7% Pervio	us Area	
0.	.249		52.5	3% Imperv	ious Area	
_	_					
Tc	Leng		Slope	Velocity	Capacity	Description
(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)	
5.0						Direct Entry,

Subcatchment DA-1B: PARKING LOT



Page 16


Summary for Subcatchment DA-1C: CLUB HOUSE AND CART PATH

Runoff = 0.49 cfs @ 12.08 hrs, Volume= 0.035 af, Depth= 1.96"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 10-YR MASHPEE ATLAS Rainfall=5.00"

_	Area ((ac)	CN	Desc	ription							
	0.0	088	88 39 >75% Grass cover, Good, HSG A									
	0.0	0.014 30 Woods, Good, HSG A										
	0.	0.111 98 Paved roads w/curbs & sewers, HSG A										
	0.3	213	69	Weig	hted Aver	age						
	0.	102		47.89	9% Pervio	us Area						
	0.	111		52.1°	1% Imperv	ious Area						
	Тс	Leng		Slope	Velocity	Capacity	Description					
_	(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)						
	5.0						Direct Entry					

Subcatchment DA-1C: CLUB HOUSE AND CART PATH



Page 17


Summary for Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND

Runoff = 0.10 cfs @ 12.15 hrs, Volume= 0.017 af, Depth= 0.49"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 10-YR MASHPEE ATLAS Rainfall=5.00"

	Area	(ac)	CN	Desc	ription		
	0.	356	39	>75%	√ Grass co	over, Good	, HSG A
	0.	051	98	Pave	d parking,	HSG A	
	0.	407	46	Weig	hted Aver	age	
	0.	356		87.4	7% Pervio	us Area	
	0.	051		12.5	3% Imperv	ious Area	
	_						
	Тс	Leng		Slope	Velocity	Capacity	Description
_	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)	
	5.0						Direct Entry, L1

Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND



Page 18


Summary for Subcatchment R1: ROOF

Runoff = 0.55 cfs @ 12.07 hrs, Volume= 0.044 af, Depth= 4.76"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 10-YR MASHPEE ATLAS Rainfall=5.00"

	Area	(ac)	CN	Desc	cription		
	0.	110	98	Roof	s, HSG A		
	0.	110		100.	00% Impe	rvious Area	1
	Тс	Lengt	h S	Slope	Velocity	Capacity	Description
	(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)	·
'	5.0				•		Direct Entry, Minimum

Subcatchment R1: ROOF



2014-009 CLUB RMS PROPOSED WIT Type III 24-hr 10-YR MASHPEE ATLAS Rainfall=5.00"

Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 19

Summary for Reach SP#1: STUDY POINT #1


Inflow Area = 1.422 ac, 38.33% Impervious, Inflow Depth = 0.50" for 10-YR MASHPEE ATLAS event

Inflow = 0.59 cfs @ 12.10 hrs, Volume= 0.059 af

Outflow = 0.59 cfs @ 12.10 hrs, Volume= 0.059 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3

Reach SP#1: STUDY POINT #1



2014-009 CLUB RMS PROPOSED WIT Type III 24-hr 10-YR MASHPEE ATLAS Rainfall=5.00"

Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

<u>Page 20</u>

Summary for Pond P-1: POND/BIOSWALE

Inflow Area = 0.584 ac, 61.47% Impervious, Inflow Depth = 1.96" for 10-YR MASHPEE ATLAS event

Inflow = 1.60 cfs @ 12.09 hrs, Volume= 0.095 af

Outflow = 0.10 cfs @ 13.68 hrs, Volume= 0.095 af, Atten= 94%, Lag= 95.3 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3 Peak Elev= 17.95' @ 13.68 hrs Surf.Area= 1,793 sf Storage= 1,883 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 200.9 min (982.5 - 781.6)

Volume	Invert	Avai	l.Storage	Storage Description	on				
#1	16.50'		4,156 cf	Custom Stage Da	Custom Stage Data (Irregular)Listed below (Recalc)				
Elevation (fee		urf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)			
16.5	50	831	207.0	0	0	831			
17.0	00	1,150	217.0	493	493	1,185			
18.0	00	1,829	236.0	1,476	1,970	1,906			
19.0	00	2,564	255.0	2,186	4,156	2,688			
Device	Routing	lnv	vert Outle	et Devices					
#1	Discarded	16	.50' 2.41	0 in/hr Exfiltration	over Surface are	ea ea			
#2	Primary	18	.00' 5.0' l	long x 9.0' breadt	h Broad-Crested	Rectangular Weir			
			Head	d (feet) 0.20 0.40	0.60 0.80 1.00 1	1.20 1.40 1.60 1.80 2.00			
			2.50	3.00 3.50 4.00 4	1.50 5.00 5.50				
			Coef	f. (English) 2.46 2	.55 2.70 2.69 2.6	88 2.68 2.67 2.64 2.64			
			2.64	2.65 2.64 2.65 2	2.65 2.66 2.67 2.	69			

Discarded OutFlow Max=0.10 cfs @ 13.68 hrs HW=17.95' (Free Discharge) 1=Exfiltration (Exfiltration Controls 0.10 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=16.50' TW=0.00' (Dynamic Tailwater) 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)


Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 21

Pond P-1: POND/BIOSWALE



2014-009 CLUB RMS PROPOSED WIT Type III 24-hr 10-YR MASHPEE ATLAS Rainfall=5.00"

Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 22

Summary for Pond P-2: FOREBAY

Inflow Area = 0.474 ac, 52.53% Impervious, Inflow Depth = 1.96" for 10-YR MASHPEE ATLAS event

Inflow = 1.09 cfs @ 12.08 hrs, Volume= 0.077 af

Outflow = 1.08 cfs @ 12.09 hrs, Volume= 0.077 af, Atten= 1%, Lag= 0.8 min

Discarded = 0.02 cfs @ 13.68 hrs, Volume= 0.026 af Primary = 1.06 cfs @ 12.09 hrs, Volume= 0.052 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3

Peak Elev= 17.95' @ 13.68 hrs Surf.Area= 409 sf Storage= 380 cf

Plug-Flow detention time= 68.9 min calculated for 0.077 af (100% of inflow)

Center-of-Mass det. time= 69.1 min (918.4 - 849.3)

Volume	Inve	rt Avail.Si	torage	Storage Description	1	
#1	16.50	0'	640 cf	Custom Stage Dat	a (Irregular)Listed	below (Recalc)
Elevati	on S	Surf.Area	Perim.	Inc.Store	Cum.Store	Wet.Area
(fee	et)	(sq-ft)	(feet)	(cubic-feet)	(cubic-feet)	(sq-ft)
16.	50	136	47.0	0	0	136
17.0	00	215	58.0	87	87	232
17.	50	310	68.0	131	218	337
18.	00	420	79.0	182	399	471
18.	50	547	89.0	241	640	611
Device	Routing	Inver	t Outle	et Devices		
#1	Discarde	16.50	2.41	0 in/hr Exfiltration	over Surface area	
#2	Primary	17.50	' 5.0' l	ong x 6.0' breadth	Broad-Crested R	lectangular Weir
			Head	d (feet) 0.20 0.40 0	0.60 0.80 1.00 1.2	20 1.40 1.60 1.80 2.00
			2.50	3.00 3.50 4.00 4.5	50 5.00 5.50	
			Coef	. (English) 2.37 2.5	1 2.70 2.68 2.68	2.67 2.65 2.65 2.65
			2.65	2.66 2.66 2.67 2.0	69 2.72 2.76 2.83	3

Discarded OutFlow Max=0.02 cfs @ 13.68 hrs HW=17.95' (Free Discharge) **1=Exfiltration** (Exfiltration Controls 0.02 cfs)

Primary OutFlow Max=1.05 cfs @ 12.09 hrs HW=17.70' TW=17.24' (Dynamic Tailwater) 2=Broad-Crested Rectangular Weir (Weir Controls 1.05 cfs @ 1.06 fps)


Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

Page 23

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Pond P-2: FOREBAY



Page 24


Summary for Subcatchment DA-1A: GRASS ABUTTING EXISTING POND

Runoff = 0.13 cfs @ 12.11 hrs, Volume= 0.014 af, Depth= 0.79"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 25-YR MASHPEE ATLAS Rainfall=5.98"

	Area	(ac)	CN	Desc	cription		
	0.	194	39	>75%	6 Grass co	over, Good	d, HSG A
	0.	024	98	Pave	ed roads w	/curbs & se	ewers, HSG A
	0.	218	45	Weig	hted Aver	age	
	0.	194		88.99	9% Pervio	us Area	
	0.	024		11.0	1% Imperv	ious Area	
	-		41.	01	V/-1	0	D
	Tc	Leng		Slope	Velocity	Capacity	Description
_	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)	
	5.0						Direct Entry,

Subcatchment DA-1A: GRASS ABUTTING EXISTING POND



Page 25


Summary for Subcatchment DA-1B: PARKING LOT

Runoff = 1.53 cfs @ 12.08 hrs, Volume= 0.107 af, Depth= 2.70"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 25-YR MASHPEE ATLAS Rainfall=5.98"

Area	(ac)	CN	Desc	cription		
0.	.197	39	>75%	√ Grass co	over, Good	d, HSG A
0.	.028	30	Woo	ds, Good,	HSG A	
0.	.249	98	Pave	ed parking	HSG A	
0.	.474	69	Weig	hted Aver	age	
0.	.225		47.4	7% Pervio	us Area	
0.	.249		52.5	3% Imperv	ious Area	
_	_					
Tc	Leng		Slope	Velocity	Capacity	Description
(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)	
5.0						Direct Entry,

Subcatchment DA-1B: PARKING LOT



Page 26


Summary for Subcatchment DA-1C: CLUB HOUSE AND CART PATH

Runoff = 0.69 cfs @ 12.08 hrs, Volume= 0.048 af, Depth= 2.70"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 25-YR MASHPEE ATLAS Rainfall=5.98"

_	Area ((ac)	CN	Desc	ription							
	0.0	088	88 39 >75% Grass cover, Good, HSG A									
	0.0	0.014 30 Woods, Good, HSG A										
	0.	0.111 98 Paved roads w/curbs & sewers, HSG A										
	0.3	213	69	Weig	hted Aver	age						
	0.	102		47.89	9% Pervio	us Area						
	0.	111		52.1°	1% Imperv	ious Area						
	Тс	Leng		Slope	Velocity	Capacity	Description					
_	(min)	(fee	t)	(ft/ft)	(ft/sec)	(cfs)						
	5.0						Direct Entry					

Subcatchment DA-1C: CLUB HOUSE AND CART PATH



Page 27


Summary for Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND

Runoff = 0.27 cfs @ 12.11 hrs, Volume= 0.029 af, Depth= 0.86"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 25-YR MASHPEE ATLAS Rainfall=5.98"

/	Area (a	ac)	CN	Desc	ription		
	0.3	356	39	>75%	6 Grass co	over, Good	, HSG A
	0.0)51	98	Pave	ed parking,	, HSG A	
	0.4	107	46	Weig	hted Aver	age	
	0.3	356		87.4	7% Pervio	us Area	
	0.0)51		12.5	3% Imperv	ious Area	
		Lengtl	ո Տ	Slope	Velocity	Capacity	Description
<u>(r</u>	min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	5.0						Direct Entry, L1

Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND



Page 28


Summary for Subcatchment R1: ROOF

Runoff = 0.66 cfs @ 12.07 hrs, Volume= 0.053 af, Depth= 5.74"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 25-YR MASHPEE ATLAS Rainfall=5.98"

	Area	(ac)	CN	Desc	cription		
	0.	110	98	Roof	s, HSG A		
_	0.	110		100.0	00% Impe	rvious Area	1
	Tc	Lengt	h S	Slope	Velocity	Capacity	Description
	(min)	(feet	t)	(ft/ft)	(ft/sec)	(cfs)	·
	5.0						Direct Entry, Minimum

Subcatchment R1: ROOF



2014-009 CLUB RMS PROPOSED WIT Type III 24-hr 25-YR MASHPEE ATLAS Rainfall=5.98"

Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 29

Summary for Reach SP#1: STUDY POINT #1


Inflow Area = 1.422 ac, 38.33% Impervious, Inflow Depth = 0.95" for 25-YR MASHPEE ATLAS event

Inflow = 1.07 cfs @ 12.09 hrs, Volume= 0.113 af

Outflow = 1.07 cfs @ 12.09 hrs, Volume= 0.113 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3

Reach SP#1: STUDY POINT #1



2014-009 CLUB RMS PROPOSED WIT Type III 24-hr 25-YR MASHPEE ATLAS Rainfall=5.98"

Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 30

Summary for Pond P-1: POND/BIOSWALE

Inflow Area = 0.584 ac, 61.47% Impervious, Inflow Depth = 2.70" for 25-YR MASHPEE ATLAS event

Inflow 2.13 cfs @ 12.08 hrs, Volume= 0.132 af

0.55 cfs @ 12.46 hrs, Volume= Outflow 0.132 af, Atten= 74%, Lag= 22.6 min

0.11 cfs @ 12.46 hrs, Volume= Discarded = 0.110 af Primary = 0.44 cfs @ 12.46 hrs, Volume= 0.021 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3 Peak Elev= 18.11' @ 12.46 hrs Surf.Area= 1,903 sf Storage= 2,174 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 180.3 min (969.3 - 789.1)

Volume	Invert	Avail	.Storage	Storage Description	on	
#1	16.50'		4,156 cf	Custom Stage Da	ata (Irregular)Liste	d below (Recalc)
Elevatio		urf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
16.5	50	831	207.0	0	0	831
17.0	00	1,150	217.0	493	493	1,185
18.0	00	1,829	236.0	1,476	1,970	1,906
19.0	00	2,564	255.0	2,186	4,156	2,688
Device	Routing	Inv	ert Outle	et Devices		
#1	Discarded	16.	50' 2.41	0 in/hr Exfiltration	over Surface are	
#2	Primary	18.	00' 5.0'	long x 9.0' breadt	h Broad-Crested I	Rectangular Weir
	•		Head	d (feet) 0.20 0.40	0.60 0.80 1.00 1.	20 1.40 1.60 1.80 2.00
			2.50	3.00 3.50 4.00 4	1.50 5.00 5.50	
			Coef	f. (English) 2.46 2.	.55 2.70 2.69 2.68	3 2.68 2.67 2.64 2.64
			2.64	2.65 2.64 2.65 2	2.65 2.66 2.67 2.6	9

Discarded OutFlow Max=0.11 cfs @ 12.46 hrs HW=18.11' (Free Discharge) **1=Exfiltration** (Exfiltration Controls 0.11 cfs)


Primary OutFlow Max=0.44 cfs @ 12.46 hrs HW=18.11' TW=0.00' (Dvnamic Tailwater) 2=Broad-Crested Rectangular Weir (Weir Controls 0.44 cfs @ 0.81 fps)

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 31

Pond P-1: POND/BIOSWALE



2014-009 CLUB RMS PROPOSED WIT Type III 24-hr 25-YR MASHPEE ATLAS Rainfall=5.98"

Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

<u>Page 32</u>

Summary for Pond P-2: FOREBAY

Inflow Area = 0.474 ac, 52.53% Impervious, Inflow Depth = 2.70" for 25-YR MASHPEE ATLAS event

Inflow = 1.53 cfs @ 12.08 hrs, Volume= 0.107 af

Outflow = 1.49 cfs @ 12.08 hrs, Volume= 0.107 af, Atten= 2%, Lag= 0.2 min

Discarded = 0.02 cfs @ 12.46 hrs, Volume= 0.028 af Primary = 1.47 cfs @ 12.08 hrs, Volume= 0.079 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3

Peak Elev= 18.11' @ 12.46 hrs Surf.Area= 446 sf Storage= 447 cf

Plug-Flow detention time= 56.1 min calculated for 0.106 af (100% of inflow)

Center-of-Mass det. time= 56.4 min (896.2 - 839.8)

Volume	Inve	rt Avail.Si	torage	Storage Description	1	
#1	16.50	0'	640 cf	Custom Stage Dat	a (Irregular)Listed	below (Recalc)
Elevati	on S	Surf.Area	Perim.	Inc.Store	Cum.Store	Wet.Area
(fee	et)	(sq-ft)	(feet)	(cubic-feet)	(cubic-feet)	(sq-ft)
16.	50	136	47.0	0	0	136
17.0	00	215	58.0	87	87	232
17.	50	310	68.0	131	218	337
18.	00	420	79.0	182	399	471
18.	50	547	89.0	241	640	611
Device	Routing	Inver	t Outle	et Devices		
#1	Discarde	16.50	2.41	0 in/hr Exfiltration	over Surface area	
#2	Primary	17.50	' 5.0' l	ong x 6.0' breadth	Broad-Crested R	lectangular Weir
			Head	d (feet) 0.20 0.40 0	0.60 0.80 1.00 1.2	20 1.40 1.60 1.80 2.00
			2.50	3.00 3.50 4.00 4.5	50 5.00 5.50	
			Coef	. (English) 2.37 2.5	1 2.70 2.68 2.68	2.67 2.65 2.65 2.65
			2.65	2.66 2.66 2.67 2.0	69 2.72 2.76 2.83	3


Discarded OutFlow Max=0.02 cfs @ 12.46 hrs HW=18.11' (Free Discharge) **1=Exfiltration** (Exfiltration Controls 0.02 cfs)

Primary OutFlow Max=1.48 cfs @ 12.08 hrs HW=17.75' TW=17.53' (Dynamic Tailwater) 2=Broad-Crested Rectangular Weir (Weir Controls 1.48 cfs @ 1.18 fps)

Page 33

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Pond P-2: FOREBAY



Page 34


Summary for Subcatchment DA-1A: GRASS ABUTTING EXISTING POND

Runoff = 0.31 cfs @ 12.09 hrs, Volume= 0.027 af, Depth= 1.47"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 100-YR MASHPEE ALTAS Rainfall=7.49"

	Area	(ac)	CN	Desc	cription		
	0.	194	39	>75%	6 Grass co	over, Good	d, HSG A
	0.	024	98	Pave	ed roads w	/curbs & se	ewers, HSG A
	0.	218	45	Weig	hted Aver	age	
	0.	194		88.99	9% Pervio	us Area	
	0.	024		11.0	1% Imperv	ious Area	
	-		41.	01	V/-1	0	D
	Tc	Leng		Slope	Velocity	Capacity	Description
_	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)	
	5.0						Direct Entry,

Subcatchment DA-1A: GRASS ABUTTING EXISTING POND



Page 35


Summary for Subcatchment DA-1B: PARKING LOT

Runoff = 2.24 cfs @ 12.08 hrs, Volume= 0.155 af, Depth= 3.92"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 100-YR MASHPEE ALTAS Rainfall=7.49"

_	Area	(ac)	CN	Desc	ription			_
	0.	197	39	>75%	6 Grass co	over, Good	d, HSG A	
	0.	028	30	Woo	ds, Good,	HSG A		
_	0.:	249	98	Pave	d parking,	HSG A		_
	0.4	474	69	Weig	hted Aver	age		
	0	225		47.4	7% Pervio	us Area		
	0.	249		52.53	3% Imperv	ious Area		
	_					_		
		Leng		Slope	Velocity	Capacity	Description	
_	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)		_
	5.0						Direct Entry.	

Subcatchment DA-1B: PARKING LOT



Page 36


Summary for Subcatchment DA-1C: CLUB HOUSE AND CART PATH

Runoff = 1.00 cfs @ 12.08 hrs, Volume= 0.070 af, Depth= 3.92"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 100-YR MASHPEE ALTAS Rainfall=7.49"

_	Area	(ac)	CN	Desc	ription		
	0.	880	39	>75%	ն Grass co	over, Good	d, HSG A
	0.	014	30	Woo	ds, Good,	HSG A	
_	0.	111	98	Pave	d roads w	/curbs & se	sewers, HSG A
_	0.	213	69	Weig	hted Aver	age	
	0.	102		47.89	9% Pervio	us Area	
	0.	111		52.1	1% Imperv	ious Area	
	Tc	Leng		Slope	Velocity	Capacity	Description
_	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)	
	5.0						Direct Entry.

Subcatchment DA-1C: CLUB HOUSE AND CART PATH



Page 37


Summary for Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND

Runoff = 0.64 cfs @ 12.09 hrs, Volume= 0.053 af, Depth= 1.57"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 100-YR MASHPEE ALTAS Rainfall=7.49"

A	rea (ad	c) CN	l Des	cription		
	0.35	6 39) >75°	% Grass c	over, Good	I, HSG A
	0.05	51 98	B Pave	ed parking	, HSG A	
	0.40	7 46) Wei	ghted Aver	age	
	0.35	6	87.4	7% Pervio	us Area	
	0.05	51	12.5	3% Imper	ious Area	
(m	Tc L	ength (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	5.0					Direct Entry, L1

Subcatchment DA-2: GRASS AND CART PATH ABUTTING POND



Page 38


Summary for Subcatchment R1: ROOF

Runoff = 0.83 cfs @ 12.07 hrs, Volume= 0.066 af, Depth= 7.25"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs Type III 24-hr 100-YR MASHPEE ALTAS Rainfall=7.49"

_	Area	(ac)	CN	Desc	cription		
	0.	110	98	Roof	s, HSG A		
	0.	110		100.	00% Impe	rvious Area	I
	Tc	Lengt	th S	Slope	Velocity	Capacity	Description
	(min)	(fee		(ft/ft)	(ft/sec)	(cfs)	
	5.0						Direct Entry, Minimum

Subcatchment R1: ROOF



2014-009 CLUB RMS PROPOSED WIType III 24-hr 100-YR MASHPEE ALTAS Rainfall=7.49"

Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 39

Summary for Reach SP#1: STUDY POINT #1


Inflow Area = 1.422 ac, 38.33% Impervious, Inflow Depth = 1.82" for 100-YR MASHPEE ALTAS event

Inflow = 2.61 cfs @ 12.17 hrs, Volume= 0.216 af

Outflow = 2.61 cfs @ 12.17 hrs, Volume= 0.216 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3

Reach SP#1: STUDY POINT #1



2014-009 CLUB RMS PROPOSED WIType III 24-hr 100-YR MASHPEE ALTAS Rainfall=7.49"

Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

<u>Page 40</u>

Summary for Pond P-1: POND/BIOSWALE

Inflow Area = 0.584 ac, 61.47% Impervious, Inflow Depth = 3.94" for 100-YR MASHPEE ALTAS event

Inflow = 2.59 cfs @ 12.07 hrs, Volume= 0.192 af

Outflow = 1.52 cfs @ 12.22 hrs, Volume= 0.192 af, Atten= 41%, Lag= 8.8 min

Discarded = 0.11 cfs @ 12.22 hrs, Volume = 0.126 afPrimary = 1.41 cfs @ 12.22 hrs, Volume = 0.066 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3 Peak Elev= 18.23' @ 12.22 hrs Surf.Area= 1,990 sf Storage= 2,418 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 146.0 min (938.0 - 792.0)

Volume	Inve	<u>rt Avail</u>	.Storage	Storage Description	n		
#1	16.5	0'	4,156 cf	Custom Stage Da	ta (Irregular) Listed	below (Recalc)	_
Elevation (fee		Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
16.5 17.0 18.0	50 00 00	831 1,150 1,829 2,564	207.0 217.0 236.0 255.0	0 493 1,476 2,186	0 493 1,970 4,156	831 1,185 1,906 2,688	
Device	Routing	,		et Devices	4,100	2,000	_
#1 #2	Discarde Primary		00' 5.0' Head 2.50 Coef	3.00 3.50 4.00 4.	n Broad-Crested R 0.60 0.80 1.00 1.2 50 5.00 5.50 55 2.70 2.69 2.68	Rectangular Weir 20 1.40 1.60 1.80 2.00 2.68 2.67 2.64 2.64	

Discarded OutFlow Max=0.11 cfs @ 12.22 hrs HW=18.23' (Free Discharge) 1=Exfiltration (Exfiltration Controls 0.11 cfs)

Primary OutFlow Max=1.40 cfs @ 12.22 hrs HW=18.23' TW=0.00' (Dynamic Tailwater) 2=Broad-Crested Rectangular Weir (Weir Controls 1.40 cfs @ 1.20 fps)


Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

Page 41

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Pond P-1: POND/BIOSWALE



2014-009 CLUB RMS PROPOSED WIType III 24-hr 100-YR MASHPEE ALTAS Rainfall=7.49"

Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Page 42

Summary for Pond P-2: FOREBAY

Inflow Area = 0.474 ac, 52.53% Impervious, Inflow Depth = 3.92" for 100-YR MASHPEE ALTAS event

Inflow = 2.24 cfs @ 12.08 hrs, Volume= 0.155 af

Outflow = 1.78 cfs @ 12.07 hrs, Volume= 0.155 af, Atten= 20%, Lag= 0.0 min

Discarded = 0.03 cfs @ 12.22 hrs, Volume = 0.030 afPrimary = 1.76 cfs @ 12.07 hrs, Volume = 0.125 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-30.00 hrs, dt= 0.03 hrs / 3

Peak Elev= 18.24' @ 12.22 hrs Surf.Area= 478 sf Storage= 506 cf

Plug-Flow detention time= 42.4 min calculated for 0.155 af (100% of inflow)

Center-of-Mass det. time= 42.7 min (871.7 - 829.0)

Volume	Invert	Avail.St	orage	Storage Description	on	
#1	16.50'	(640 cf	Custom Stage Da	ata (Irregular)Liste	d below (Recalc)
Elevation	on Si	urf.Area	Perim.	Inc.Store	Cum.Store	Wet.Area
(fee	et)	(sq-ft)	(feet)	(cubic-feet)	(cubic-feet)	(sq-ft)
16.	50	136	47.0	0	0	136
17.0	00	215	58.0	87	87	232
17.	50	310	68.0	131	218	337
18.0	00	420	79.0	182	399	471
18.	50	547	89.0	241	640	611
Device	Routing	Inver	t Outle	et Devices		
#1	Discarded	16.50	' 2.41	0 in/hr Exfiltration	over Surface are	 a
#2	Primary	17.50	' 5.0'	long x 6.0' breadt	h Broad-Crested	Rectangular Weir
	•		Head	d (feet) 0.20 0.40	0.60 0.80 1.00 1	.20 1.40 1.60 1.80 2.00
			2.50	3.00 3.50 4.00 4	1.50 5.00 5.50	
			Coef	f. (English) 2.37 2.	.51 2.70 2.68 2.68	8 2.67 2.65 2.65 2.65
			2.65	2.66 2.66 2.67 2	2.69 2.72 2.76 2.8	33

Discarded OutFlow Max=0.03 cfs @ 12.22 hrs HW=18.24' (Free Discharge) 1=Exfiltration (Exfiltration Controls 0.03 cfs)

Primary OutFlow Max=1.75 cfs @ 12.07 hrs HW=17.98' TW=17.94' (Dynamic Tailwater) 2=Broad-Crested Rectangular Weir (Weir Controls 1.75 cfs @ 0.73 fps)


Prepared by BAXTER-NYE ENGINEERING

Printed 4/14/2020

Page 43

HydroCAD® 10.00-21 s/n 04803 © 2018 HydroCAD Software Solutions LLC

Pond P-2: FOREBAY



APPENDIX C

SITE SOIL INFORMATION

- SOIL SURVEY MAPS AND MAP UNITS.
- CLASSIFICATION AND DESCRIPTION OF SOILS ON SITE.




MAP LEGEND

Area of Interest (AOI)

Area of Interest (AOI)

Soils

Soil Map Unit Polygons



Soil Map Unit Points

Special Point Features

Blowout

Borrow Pit

Clay Spot

Closed Depression

Gravel Pit

Gravelly Spot

Landfill

Lava Flow

Marsh or swamp

Mine or Quarry

Miscellaneous Water

Perennial Water

Rock Outcrop

Saline Spot

Sandy Spot

Severely Eroded Spot

Sinkhole

Slide or Slip

Sodic Spot

CLIAD

Spoil Area

Stony Spot

Very Stony Spot

Wet Spot

Other

Special Line Features

Water Features

Streams and Canals

Transportation

Rails

Interstate Highways

US Routes

Major Roads

Local Roads

Background

Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:25.000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Barnstable County, Massachusetts Survey Area Data: Version 16, Sep 12, 2019

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jul 10, 2018—Nov 17, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
2t2qj	Freetown coarse sand, 0 to 3 percent slopes, sanded surface	3.0	26.7%
2xfg8	Deerfield loamy fine sand, 0 to 3 percent slopes	5.2	45.9%
2y07s	Carver loamy coarse sand, 0 to 3 percent slopes	1.5	13.8%
2y07t	Carver loamy coarse sand, 3 to 8 percent slopes	1.2	10.6%
2у07у	Carver coarse sand, 15 to 35 percent slopes	0.3	3.0%
Totals for Area of Interest		11.2	100.0%

Barnstable County, Massachusetts

2xfg8—Deerfield loamy fine sand, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 2xfg8 Elevation: 0 to 1,100 feet

Mean annual precipitation: 36 to 71 inches
Mean annual air temperature: 39 to 55 degrees F

Frost-free period: 145 to 240 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Deerfield and similar soils: 85 percent *Minor components*: 15 percent

Estimates are based on observations, descriptions, and transects of

the mapunit.

Description of Deerfield

Setting

Landform: Kame terraces, outwash plains, outwash deltas,

outwash terraces

Landform position (three-dimensional): Tread Down-slope shape: Convex, linear, concave Across-slope shape: Concave, linear, convex

Parent material: Sandy outwash derived from granite, gneiss,

and/or quartzite

Typical profile

Ap - 0 to 9 inches: loamy fine sand Bw - 9 to 25 inches: loamy fine sand BC - 25 to 33 inches: fine sand Cg - 33 to 60 inches: sand

Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Moderately well drained

Runoff class: Negligible

Capacity of the most limiting layer to transmit water (Ksat):
Moderately high to very high (1.42 to 99.90 in/hr)

Depth to water table: About 15 to 37 inches

Frequency of flooding: None Frequency of ponding: None

Salinity, maximum in profile: Nonsaline (0.0 to 1.9 mmhos/cm)

Sodium adsorption ratio, maximum in profile: 11.0

Available water storage in profile: Moderate (about 6.5 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2w

Hydrologic Soil Group: A Hydric soil rating: No

Minor Components

Windsor

Percent of map unit: 7 percent

Landform: Outwash plains, outwash deltas, kame terraces,

outwash terraces

Landform position (three-dimensional): Tread Down-slope shape: Linear, concave, convex Across-slope shape: Concave, linear, convex

Hydric soil rating: No

Wareham

Percent of map unit: 5 percent

Landform: Depressions, drainageways

Down-slope shape: Concave Across-slope shape: Concave

Hydric soil rating: Yes

Sudbury

Percent of map unit: 2 percent

Landform: Outwash deltas, kame terraces, outwash plains,

outwash terraces

Landform position (three-dimensional): Tread Down-slope shape: Linear, convex, concave Across-slope shape: Convex, concave, linear

Hydric soil rating: No

Ninigret

Percent of map unit: 1 percent

Landform: Outwash plains, kame terraces, outwash terraces

Landform position (three-dimensional): Tread

Down-slope shape: Convex, linear Across-slope shape: Convex, concave

Hydric soil rating: No

Data Source Information

Soil Survey Area: Barnstable County, Massachusetts

Survey Area Data: Version 16, Sep 12, 2019



16 Great Neck Road North Mashpee, Massachusetts 02649

Mr. Jan Aggerbeck, Owner Cape Cod Coffee 10 Evergreen Circle Mashpee, MA 02649

Re: Restoration of cleared area with placement of temporary fill

June 18, 2020

Mr. Aggerbeck,

As you are aware the Planning Board met on 6/17/2020 and discussed the inspection report by the Consulting Engineer Charles Rowley dated 6/11/2020. In his report he noted, "... there is a significant amount of clearing and placement of temporary fill starting at Evergreen Circle that is within the area that was marked on Sheet 3 of 6 of the approved plan of September 3, 2019 as "Area to remain in its natural state.""

In response to the engineer's letter, Brian Catignani, project manager, wrote on June 15, 2020 that, "the property owner intends to revegetate this "disturbed" area with similar native plantings following construction activity at the front of the property."

It was the consensus of the board that the proposed remedy to revegetate the specified area was adequate but directed me to further communicate that prior to revegetating the area, all temporary fill must be removed. While the Board is confident that was your intention, it was not specifically clarified in Mr. Catignani's letter.

This issue will be rectified upon the satisfactory removal of the temporary fill and revegation of the area with similar native plantings. No additional action will be necessary if these conditions are met. Charlie Rowley is expected to communicate the same, in person, at his next inspections.

Thank you,

Evan R. Lehrer Town Planner

Cc: Brian Catignani (via email) Charlie Rowley (via email)

PIERCE ATWOODS

MICHELLE N. O'BRIEN

100 Summer Street #2250 Boston, MA 02110

P 617.488.8146 **F** 617.824.2020 mobrien@pierceatwood.com www.pierceatwood.com

Admitted in: MA, ME

June 15, 2020

Via Electronic Mail elehrer@mashpeema.gov

Evan R. Lehrer Town Planner Town of Mashpee 16 Great Neck Road North Mashpee, Massachusetts 02649

RE: SouthCape Village Special Permit

Notice of Intention to Sell Property and Transfer Special Permit

Dear Mr. Lehrer:

Thank you for your letter of June 12, 2020 notifying me of the Planning Board's approval of my request, submitted on behalf of DPF Mashpee LLC, to allow less than 90 days' notice for transfer of the above-referenced special permit. The sale of the property is not going forward at this time. Accordingly, there is no need to transfer the permit.

Thank you for your consideration.

Michelle N. O'Brien

Very truly yours,

Michelle N. O'Brien



eDEP Transaction Copy

Here is the file you requested for your records.

To retain a copy of this file you must save and/or print.

Username: EBELAIR

Transaction ID: 1198905

Document: Groundwater Discharge Monitoring Report Forms

Size of File: 1029.15K

Status of Transaction: Submitted

Date and Time Created: 6/22/2020:6:34:08 AM

Note: This file only includes forms that were part of your transaction as of the date and time indicated above. If you need a more current copy of your transaction, return to eDEP and select to "Download a Copy" from the Current Submittals page.



Bureau of Resource Protection - Groundwater Discharge Program

Groundwater Permit

DISCHARGE MONITORING REPORT

668			
1. Pern	nit Numbe	r	
2. Tax i	dentificati	on Number	
2020 N	MAY MON	ITHLY	
3. Sam	plina Mon	th & Freque	ncv

A. Facility Information

Important:When

filling out forms on the computer, use only the tab key to move your cursor do not use the return key.





Facility name, address:			
SOUTH CAPE VILLAGE			
a. Name			
672 FALMOUTH ROAD/RTE. 28			
b. Street Address			
MASHPEE	MA	02649	
c. City	d. State	e. Zip Code	
Contact information:			
MYLES OSTROFF			
a. Name of Facility Contact Person			
6174311097	myles@	chartweb.com	
		address	

RI ANALYTICAL

b. Laboratory Name

B. Form Selection

3. Sampling information:

a. Date Sampled (mm/dd/yyyy)

c. Analysis Performed By (Name)

NICOLE SKYLESON

5/7/2020

1. Please select Form Type and Sampling Month & Frequency

	Discharge Monitoring Report - 2020 May Monthly	•
	All forms for submittal have been completed.	
2.	$\overline{}$ This is the last selection.	
3.	Delete the selected form.	



Bureau of Resource Protection - Groundwater Discharge Program

Groundwater Permit

DISCHARGE MONITORING REPORT

668	
1. Permit Number	
1. Permit Number	

2020 MAY MONTHLY
3. Sampling Month & Frequency

2. Tax identification Number

D. Contaminant Analysis Information

- For "0", below detection limit, less than (<) value, or not detected, enter "ND"
- TNTC = too numerous to count. (Fecal results only)
- NS = Not Sampled

1. Parameter/Contaminant	2. Influent	3. Effluent	4. Effluent Method
Units			Detection limit
BOD	54	28	8.0
MG/L	,	,	
TSS	72	4.7	2.0
MG/L	,	,	
TOTAL SOLIDS	430		
MG/L	-		
AMMONIA-N	9.8		
MG/L			
NITRATE-N		2.2	0.25
MG/L		,-	
TOTAL NITROGEN(NO3+NO2+TKN)		5.1	0.25
MG/L		Þe-	
OIL & GREASE		ND	0.5
MG/I			. ,



Bureau of Resource Protection - Groundwater Discharge Program

Groundwater Permit

DAILY LOG SHEET

668	
Permit Number	
2. Tax identification Number	
2020 MAY DAILY	
3. Sampling Month & Frequency	

A. Facility Information

Important:When

filling out forms on the computer, use only the tab key to move your cursor do not use the return key.





•	

1. Facility name, address:			
SOUTH CAPE VILLAGE			
a. Name			
672 FALMOUTH ROAD/RTE. 28			
b. Street Address			
MASHPEE	MA	02649	
c. City	d. State	e. Zip Code	
MYLES OSTROFF a. Name of Facility Contact Person 6174311097	myles@	⊋chartweb.com	
b. Telephone Number	c. e-mail	address	
3. Sampling information:			
5/31/2020	WHITE	WATER	
a. Date Sampled (mm/dd/yyyy)	b. Labora	atory Name	
LAURA JOHNSON			
c. Analysis Performed By (Name)			

B. Form Selection

1. Please select Form Type and Sampling Month & Frequency

	Daily Log Sheet - 2020 May Daily	-
	All forms for submittal have been completed.	
2.	This is the last selection.	
3	— Delete the selected form	



Bureau of Resource Protection - Groundwater Discharge Program

Groundwater Permit

DAILY LOG SHEET

668

1. Permit Number

2. Tax identification Number

2020 MAY DAILY
3. Sampling Month & Frequency

C. Daily Readings/Analysis Information

Date	Effluent Flow GPD	Reuse Flow GPD	Irrigation Flow GPD	Turbidity	Influent pH	Effluent pH	Chlorine Residual (mg/l)	UV Intensity (%)
1	7798					7.4		
2	7799							
3	7798							
4	3871					7.4		
5	7617					7.4		
6	7664					7.4		
7	7735					7.4		
8	7678					7.4		
9	7678							
10	7677							
11	7539					7.4		
12	7923					7.3		
13	7583					7.4		
14	7514					7.3		
15	7558					7.3		
16	7558							
17	7557							
18	6671					7.3		
19						7.3		
20	3700							
21	6722					7.4		
22	7740					7.4		
23	7740							
24	7740							
25	7740							
26	7497					7.5		
27	7667					7.4		
28	7514					7.4		
29	8760					7.4		
30	8761							
31	8761							



Bureau of Resource Protection - Groundwater Discharge Program

Groundwater Permit

MONITORING WELL DATA REPORT

	668 . Permit Number
2	. Tax identification Number
- 1-	2020 MAY MONTHLY . Sampling Month & Frequency

A. Facility Information

Important:When

filling out forms on 1 the computer, use only the tab key to move your cursor - do not use the return key.





1. Facility name, address:			
SOUTH CAPE VILLAGE			
a. Name			
672 FALMOUTH ROAD/RTE. 2	8		
b. Street Address			
MASHPEE	MA	02649	
c. City	d. State	e. Zip Code	
2. Contact information:			
MYLES OSTROFF			
MYLES OSTROFF	myles@	chartweb.com	
MYLES OSTROFF a. Name of Facility Contact Person	myles@ c. e-mail a		
MYLES OSTROFF a. Name of Facility Contact Person 6174311097			
MYLES OSTROFF a. Name of Facility Contact Person 6174311097 b. Telephone Number		ddress	
MYLES OSTROFF a. Name of Facility Contact Person 6174311097 b. Telephone Number 3. Sampling information:	c. e-mail a	ddress VATER	

B. Form Selection

c. Analysis Performed By (Name)

1. Please select Form Type and Sampling Month & Frequency

	Monitoring Well Data Report - 2020 May Monthly	•
	All forms for submittal have been completed.	
2.	This is the last selection.	
3.	Delete the selected form.	



Bureau of Resource Protection - Groundwater Discharge Program

Groundwater Permit

MONITORING WELL DATA REPORT

668

1. Permit Number

2. Tax identification Number

2020 MAY MONTHLY

3. Sampling Month & Frequency

C. Contaminant Analysis Information

• For "0", below detection limit, less than (<) value, or not detected, enter "ND"

• TNTC = too numerous to count. (Fecal results only)

- NS = Not Sampled
- DRY = Not enough water in well to sample.

Parameter/Contaminant	P-1	P-2	P-4	P-6		
Units	Well #: 1	Well #: 2	Well #: 3	Well #: 4	Well #: 5	Well #: 6
PH 5	.39	5.92	5.66	6.44		
S.U.						
STATIC WATER LEVEL 1	7.15	46.28	50.9	49.42		
FEET		1	,	,		
SPECIFIC CONDUCTANCE 6	30	248	233	1231		
UMHOS/C			<u> </u>			



Bureau of Resource Protection - Groundwater Discharge Program


Groundwater Permit

668	
4 D '(M	
Permit Number	

2. Tax identification Number

Facility Information

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.







Any person signing a document under 314 CMR 5.14(1) or (2) shall make the following certification

If you are filing electronic-ally and want to attach additional comments, select the check box.

Certification

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that the are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

ELIZABETH BELAIR	6/16/2020
a. Signature	b. Date (mm/dd/yyyy)

Reporting Package Comments

PLANT MET ALL PERMIT REQUIREMENTS FOR MAY 2020.

ı	